

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-047-21351-00-00
Spot: S2SE Sec/Twnshp/Rge: 32-25S-16W
671 feet from S Section Line, 1338 feet from E Section Line
Lease Name: ENGLISH Well #: 1
County: EDWARDS Total Vertical Depth: 4800 feet

Operator License No.: 5893
Op Name: PRATT WELL SERVICE, INC.
Address: PO BOX 847
PRATT, KS 67124

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		3720		WITH 2 SX CMT
CIBP		4420		WITH 2 SX CMT
PROD 5.5		4800	1666	WITH 250 SX CMT
SURF 8.625		350		WITH 200 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/21/2012 8:30 AM
Plug Co. License No.: 5893 Plug Co. Name: PRATT WELL SERVICE, INC.
Proposal Rcvd. from: GARELD INSLEE Company: PRATT WELL SERVICE, INC. Phone: (620) 672-9571

Proposed Plugging Method: CIBP @ 4420' & 2 SX CMT. CIBP @ 3720' & 2 SX CMT. PLUG AT 1100' WITH 15 SX GEL & 50 SX CMT. PLUG AT 380' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY Witness Type: PARTIAL
Date/Time Plugging Completed: 12/21/2012 1:00 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP'S @ 4420' & 3720'. PUT 2 SX CMT ON TOP OF EACH CIBP. 1ST PLUG AT 1111' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 373' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4593	4598		
4473	4479		
3774	3792		

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: CSG

District: 01

Signed Stephen Pfeifer
2/27/13 (TECHNICIAN)

RECEIVED

DEC 27 2012

KCC DODGE CITY

RECEIVED
JAN 07 2013
KCC WICHITA