

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-23890-00-00
Spot: W2NENESW Sec/Twnshp/Rge: 18-6S-23W
2310 feet from S Section Line, 2200 feet from W Section Line
Lease Name: CAMPBELL Well #: 18-2
County: GRAHAM Total Vertical Depth: 3926 feet

Operator License No.: 8914
Op Name: H & C OIL OPERATING INC.
Address: PO BOX 86
PLAINVILLE, KS 67663

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	280		165 sx

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 02/21/2013 12:00 AM
Plug Co. License No.: 33493 Plug Co. Name: AMERICAN EAGLE DRILLING LLC
Proposal Rcvd. from: BRAD Company: AMERICAN EAGLE DRILLING LLC Phone: (785) 302-0476

Proposed Plugging Method: Ordered 205 sx 60/40 pozmix - 4% gel cement with 1/4# flo- seal per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: EDWIN SCHUMACHER WitnessType: NONE
Date/Time Plugging Completed: 02/21/2013 12:30 AM KCC Agent: EDWIN SCHUMACHER

Actual Plugging Report:

1st plug @2140 w/25 sx
2nd plug @1285 w/100 sx
3rd plug @330 w/40 sx
4th plug @40 w/10 sx

Rathole 30 sx

Perfs:

Remarks: QUALITY

Plugged through: DP

RECEIVED
MAR 04 2013
KCC WICHITA

District: 04

Signed Ed Schumacher
3/08/13 (TECHNICIAN)

CM

3-4-13 2:30 2013