

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-20907-00-01
Spot: NWSW Sec/Twnshp/Rge: 29-27S-9W
1980 feet from S Section Line, 4620 feet from E Section Line
Lease Name: MOLITOR Well #: 1
County: KINGMAN Total Vertical Depth: 4718 feet

Operator License No.: 5237

Op Name: PLANO PETROLEUM CORPORATION

Address: 1101 E PLANO PKWY STE C PO BOX 860247
PLANO, TX 75074

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3991		
PROD	4.5	4116	2300	150 SX
SURF	8.625	248		225 SX

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 03/29/2013 8:00 AM

Plug Co. License No.: 5105

Plug Co. Name: CLARKE CORPORATION

Proposal Rcvd. from: MARK MORGENSON

Company:

Phone: (620) 866-5665

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: STEVE VANGIESON

Witness Type: PARTIAL

Date/Time Plugging Completed: 03/29/2013 1:00 PM

KCC Agent: B. J. HOPE

Actual Plugging Report:

SANDED BACK TO 3730' - CAPPED WITH 4 SX CEMENT ON TOP. CUT CASING PIPE OFF @ 2300' PULLED CASING. RAN TUBING TO 1400' PUMPED 10 SX GEL, THEN SPOTTED 35 SX COMMON CEMENT. RAN TUBING TO 900' SPOTTED 35 SX OF CEMENT. RAN TUBING TO 300' CIRCUALTED TO SURFACE WITH 130 SX CEMENT.

Perfs:

Top	Bot	Thru	Comments
4020	4030		
3991	3991		
3825	3830		

RECEIVED
KANSAS CORPORATION COMMISSION

Remarks: ALLIED OUT OF MEDICINE LODGE WERE CEMENTERS. DENIED TA

APR 23 2013

Plugged through: TBG

CONSERVATION DIVISION
WICHITA, KS

District: 02

Signed

(TECHNICIAN)