

15-077-00271-  
000

State of Kansas

FORM - CP-2



JOHN ANDERSON, Jr. Governor  
RICHARD C. BYRD Chairman  
ALVIN F. GRAUERHOLZ Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

JAN 2 1964

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Dear Sir:

Mr. Earl Rowe of Stelbar Oil Corp., Inc. has this  
date requested permission to plug the following described well:

Mr. Rowe guarantees payment of the plugging fee.

Operator's full Name: Stelbar Oil Corporation Inc.

Complete Address: 310 Petroleum Bldg., Wichita, Kansas

Lease Name: Harrison Well No. # 1

Location: C SE NW Sec. 22 Twp. 33 Rge. 6 (E) (W) W

County Harper Total Depth 4529 Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Rowe was instructed to plug the well as follows:

275' of 8 5/8" surface pipe, cement circulated. Fill hole  
with mud to 270', 1st cementing plug, bridge with hulls,  
cement with 25 sacks. Fill hole with mud to 40', 2nd  
cementing plug, bridge with hulls, cement with 10 sacks to  
base cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving  
Conservation Division Agent