

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JAN 15 1973
1-15-73
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Baker of N C R A has this

date requested permission to plug the following described well:

Mr. Baker guarantees payment of the plugging fee.

Operator's full Name: National Cooperative Refinery Association

Complete Address: Box 6 Great Bend, Kansas

Lease Name: Murray Well No. 1

Location: SW NE Sec. 32 Twp. 18 Rge. (E)(W) 19

County: Rush Total Depth 4075' Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Baker was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 550' and displace

70 sk cmt thru drill pipe. Heavy mud to 260' set cementing plug and

displace 25 sk cmt thru drill pipe. Heavy mud to 40' set cementing

plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

Very truly yours,

Geo. F. Warrick
Conservation Division Agency