

State of Kansas



ROBERT B. DOCKING
DALE E. SAFFELS
JULES V. DOTY
JAMES O. GREENLEAF
RAYMOND B. HARVEY
JACK GLAVES

Governor
Chairman
Commissioner
Commissioner
Secretary
Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
NOV 6 1960
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Oller of Murfin Drlg. has this

date requested permission to plug the following described well:

Mr. Oller guarantees payment of the plugging fee.

Operator's full Name: Yucca Petroleum Co.

Complete Address: P. O. Box 2585 Amarillo, Texas

Lease Name: Dirks Well No. 1

Location: C NW NW Sec. 3 Twp. 19 Rge. 17 (E)(W) XX

County: Rush Total Depth 3900 Oil Well

Gas Well Input Well AWD Well D & A XX Lost Hole

Mr. Oller was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 500' and displace

50 sc cement thru drill pipe. Heavy mud to 40' set cementing plug and

1/2 sc hulls and 10 sc cement to base of cellar. Plug rat hole with

2 sc cement.

Very truly yours,

Conservation Division Agent