

State of Kansas



ROBERT B. DOCKING
DALE E. SAFFELS
JULES V. DOTY
JAMES O. GREENLEAF
RAYMOND B. HARVEY
JACK GLAVES

Governor
Chairman
Commissioner
Commissioner
Secretary
Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg.

212 N. Market

WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JUL 25 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Thompson of Mack Drlg. Co. has this

date requested permission to plug the following described well:

Mr. Thompson guarantees payment of the plugging fee.

Operator's full Name: Mack Oil Co.

Complete Address: 812 Union Center Wichita, Ks.

Lease Name: Anderson Well No. 1

Location: SW SW SE Sec. 9 Twp. 18 Rge. 19 (E)(W) X

County: Rush Total Depth 4050 Oil Well

Gas Well Input Well S&W Well D & A X Lost Hole

Mr. Hill was instructed to plug the well as follows:
Gun pits, circulate heavy mud, set cementing plug at 500' and displace
70 sc cement thru drill pipe. Heavy mud to 300' set cementing plug and
displace 20 sc cement thru drill pipe. Heavy mud to 40' set cementing
plug, 1/2 sc hulls and 10 sc cement to base of cellar. Plug rat hole
with 2 sc cement.

Very truly yours,

Leo F. Mansur
Conservation Division Agent