

15-165-00296-0000

WELL PLUGGING RECORD

FORMATION PLUGGING RECORD


STATE OF KANSAS STATE CORPORATION COMMISSION

Give All Information Completely Make Required Affidavit Mail or Deliver Report to: Conservation Division State Corporation Commission 800 Bitting Building Wichita, Kansas

Strike out upper line when reporting plugging of formations.

Rush County, Sec. 17 Twp. 19S Rge. 18 (E) W (W)

Location as "NE 1/4 NW 1/4 SW 1/4" or footage from lines CSL SW SE
Lease Owner The Vickers Petroleum Co., Inc.
Lease Name Steitz Well No. 1
Office Address Wheeler-Kelly-Hagney Bldg., Wichita, Kansas.
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 12-4-42 19 42
Application for plugging filed 12-3-42 19 42
Application for plugging approved 12-3-42 19 42
Plugging commenced 12-4-42 19 42
Plugging completed 12-4-42 19 42
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above Section Flat


If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well C. T. Alexander
Producing formation Arbuckle Dolomite Depth to top 4035 Bottom 4085 Total Depth of Well 4085 Feet

OIL, GAS OR WATER RECORDS CASING RECORD

Table with columns: Formation, Content, From, To, Size, Put In, Pulled Out. Rows include Anydrite, Topeka, Lansing Kansas City, Conglomerate, Arbuckle Dolomite.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from 248' feet to 248' feet for each plug set. Filled with mud from 4085' to 248'. Set Bridge at 248', cemented with 20 sacks. Cement mixed by Sun Cement Company, and pumped through drill pipe on bridge; Filled to within 26' of top. Set bridge and cemented to 6' of top.



12-8-42

(If additional description is necessary, use BACK of this sheet)
Correspondence regarding this well should be addressed to Mr. John Little
The Vickers Petroleum Co., Inc., Wheeler-Kelly-Hagney Bldg., Wichita, Kansas
Address

STATE OF Kansas, COUNTY OF Sedgwick, ss. JOHN M. LITTLE (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) John M Little (Address)

SUBSCRIBED AND SWORN to before me this 9th day of December 19 42

My commission expires Oct. 24, 1944 Notary Public.

15-165-00296-0000

THE VICKERS PETROLEUM CO.? INC.

Steitz No. 1
CSL SW SE Sec. 17, T.19S, R.18W.
Rush County, Kansas.

Casing Record:
240' of 10 3/4" Cemented with
200 sacks.

Commenced 11-18-42
Completed 12-4-42

Formation Tops
Top Anhydrite ----- 1260
Top Topeka ----- 3260
Top Lansing K.C. ----- 3560
Top Conglomerate ----- 3980
Top Arbuckle Dolomite -- 4035

<u>L O G</u>	0 - 300
Sand, Shale, Red Rock	300 - 1030
Red Bed & Shale	1030 - 1250
Shale	1250 - 1260
Anhydrite	1260 - 1280
Shale & Shells	1280 - 1645
Shale, Salt & Red Bed	1645 - 1870
Shale & Shells	1870 - 2060
Shale	2060 - 2085
Anhydrite	2085 - 2105
Lime	2105 - 2305
Sand & Iron Pyrite	2305 - 2314
Shale & Lime	2314 - 2365
Lime	2365 - 2535
Lime & Shale	2535 - 2645
Lime	2645 - 2735
Shale & Lime	2735 - 2788
Lime & Shale	2788 - 3045
Lime	3045 - 3105
Shale & Lime	3105 - 3280
Broken Lime	3280 - 3360
Lime	3360 - 3415
Broken Lime	3415 - 3500
Lime	3500 - 3835
Shale & Lime	3835 - 3930

Lime	3930 - 3973
Sand	3973 - 3980
Conglomerate	3980 - 4035
Cherty Dolomite	4035 - 4085

Total Depth - 4085'
Dry and Abandoned.

I hereby certify that this log is true and correct to the best of my knowledge and belief.

THE VICKERS PETROLEUM CO., INC.

By A. S. Bunte
A. S. Bunte

Subscribed and sworn to before me this 27th day of Dec., 1942.

Christine Kuhn
Notary Public

My commission expires: Oct. 24, 1944.

PLUGGING
FILE SEC 17 - T - 19 - R 18 W
BOOK PAGE 52 - LINE 8

