

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
209 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-165-21,589-000

LEASE NAME Koci

WELL NUMBER 1

4,620 Ft. from S Section Line

3,630 Ft. from E Section Line

SEC. 36 TWP. 18 RGE. 18 ~~X~~ or (W)

COUNTY Rush

Date Well Completed 10-24-91

Plugging Commenced 10-24-91

Plugging Completed 10-24-91

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR R.P. Nixon Operations, Inc.

ADDRESS 207 W. 12th, Hays, KS. 67601

PHONE#(913) 628-3834 OPERATORS LICENSE NO. 5655

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 10-24-91 (date)

by Dan Goodrow (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom T.D. 3,831'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	214'	Cmtd. w/140 sax

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_ feet to \_\_\_ feet each set.  
Pump 50 sax cement @1,200' down drill pipe. Pump 40 sax cement @600' down drill pipe. Pump 40 sax cement @230' down drill pipe. Push wiper plug to 40', dump 10 sax cement on plug to cellar. Dump 15 sax cement down rat hole and 10 sax cement down mouse hole. Plug down at 12:40 PM

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Shields Drilling Co. License No. 164

Address Shields Bldg., Russell, KS. 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: R.P. Nixon Operations, Inc.

STATE OF KANSAS COUNTY OF RUSSELL, ss.

Jack P. Beeman, Sec.-Treas. (Employee of ~~Operator~~ Contractor ~~Operator~~ of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jack P. Beeman, Sec.-Treas

(Address) Shields Bldg., Russell, KS. 67665

RECEIVED  
STATE CORPORATION COMMISSION

11-13-91  
NOV 13 1991

SUBSCRIBED AND SWORN TO before me this 31st day of October, 19 91

Verna May Hutchings  
Notary Public

My Commission Expires: April 10, 1993

CONSERVATION DIVISION  
Wichita, Kansas



VERNA MAY HUTCHINGS  
State of Kansas  
My Appt. Exp. 4-10-93

Form CP-4  
Revised 05-88




# Shields

Russell, Kansas

## WELL LOG

**Operator:** R.P. Nixon Operations, Inc.  
**Well:** Koci #1  
**Commenced:** October 16, 1991  
**Completed:** October 24, 1991  
**Contractor:** Shields Drilling Co.

**Well Description:** W/2 NE NW  
 Sec. 36-18S-18W  
 Rush County, KS.



**Elevation:** 2,054' KB  
**Treatment:**  
**Production:** D & A  
**Tops:**

### CASING RECORD

Size	Run	Pulled
8 5/8"	214'	Cmtd. w/140 sax

..... Figures Indicate Bottom of Formations .....

Clay & lime	66'
Shale & sand	1,170'
Anhydrite	1,201'
Shale	2,005'
Shale & lime	3,215'
Lime	3,831' RTD

Notes

RECEIVED  
 STATE CORPORATION COMMISSION

NOV 13 1991

RUSH COUNTY DIVISION  
 RUSSELL, KANSAS