

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Rush County, Sec. 36 Twp. 18S Rge. 18 (E) (W)

Location as "NE/CNW/SW" or footage from lines SE SE NW

Lease Owner George F. Johnston, Jr., Sterling Drilling Company

Lease Name Oliverius Well No. 1

Office Address Wichita, Kansas; Sterling, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed July 28, 1955

Application for plugging filed July 28, 1955

Application for plugging approved July 28, 1955


Plugging commenced July 28, 1955

Plugging completed July 28, 1955

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Warren Horner

Producing formation Depth to top Bottom Total Depth of Well 3855 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	1175'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud.
Set bottom plug at 300' with
20 sacks cement and top plug
at 35' with 10 sacks cement
circulated to surface.

RECEIVED
STATE CORPORATION COMMISSION
AUG 3 1955
8-3-55
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sterling Drilling Company

Address Sterling, Kansas

STATE OF KANSAS, COUNTY OF RICE, ss.

F. A. Wuellner (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *F. A. Wuellner*

Sterling, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 29th day of July, 1955

Bernard Laufermilk

Notary Public.

My commission expires *My Commission Expires Jan. 22, 1958*

PLUGGING
WICHITA SEC 36 T 18 R 18 W
BOOK PAGE 139 LINE 8

STERLING DRILLING COMPANY

Sterling, Kansas

WELL LOC-----OLIVERIUS #1

Location: SE SE 1/4 Section 36-155-18N,
Rush County, Kansas

OWNER: George F. Johnston, Jr. - Sterling Drilling Company
 ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: 7-11-55 (w.r.)
 COMPLETED: 7-28-55 (w.r.)

TOTAL DEPTH: 3855'

LOG

0-380	Shale & Red Bed	
380-515	Shale	
515-800	Sand	
800-860	Shale	
860-1150	Red Bed & Shale	
1150-1160	Shale	
1160-1205	Anhydrite	
1205-1575	Shale & Shells	
1575-1880	Shale	
1880-2555	Limestone	
2555-2915	Shale & Limestone	
2915-3310	Limestone	
3310-3385	Limestone & Shale	
3385-3645	Limestone	
3645-3689	Limestone & Shale	
3689-3725	Limestone	
3725-3800	Limestone & Shale	
3800-3828	Limestone	
3828-3855	Arbuckle Limestone	T.D.

CASING RECORD

Ran 1175' of 8-5/8" surface casing with 140 sacks cement and 4 sacks calcium chloride.

PRODUCTION

Plugged & Abandoned

To Whom It May Concern: This is to certify that this is a correct record of the drillers' time sheets for the Oliverius #1 well.

STERLING DRILLING COMPANY

F. A. Wuehler
 F. A. Wuehler, Secretary

RECEIVED
 STATE CORPORATION COMMISSION
 8-3-55
 AUG 3 1955
 CONSERVATION DIVISION
 Wichita, Kansas

PLUGGING
 FILE SEC 36-118-1842
 BOOK PAGE 139 LINE 8