


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Rush County. Sec. 24 Twp. 18S Rge. 18W E/W  
Location as "NE/CNW 1/4 SW 1/4" or footage from lines  
C S/2 SW

Lease Owner J. A. ALLISON  
Lease Name Haberman Well No. 1  
Office Address 200 W. Douglas, Suite 748, Wichita, Ks.  
Character of Well (Completed as Oil, Gas or Dry Hole)  
Dry Hole



Date Well completed 4-6 1977  
Application for plugging filed 4-6 1977  
Application for plugging approved 4-6 1977  
Plugging commenced 4-6 1977  
Plugging completed 4-6 1977

Reason for abandonment of well or producing formation  
No commercial quantities of oil or gas encountered.  
If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Balthazor  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3800  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface Hole	Shale	Surf.	1109	8-5/8"	1104	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Fluid to 650', plug, 40 sx cement;  
Fluid to 240', plug, 20 sx cement;  
Fluid to 40', plug, 10 sx cement.

4-25-77

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor D N B DRILLING, INC. D N B DRILLING, INC.  
515 R. H. Garvey Building 701 First National Building  
Wichita, Kansas 67202 Wichita, Kansas 67202

STATE OF KANSAS COUNTY OF \_\_\_\_\_, ss.  
JAMES L. DONELSON (employee of owner) or (owner or operator)  
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James L. Donelson  
515 R. H. Garvey Bldg., Wichita, Kansas 67202  
(Address)

SUBSCRIBED AND SWORN TO before me this 7th day of April, 19 77

Ella Priess  
Notary Public.

My commission expires 8-25-80 Ella Priess



15-165-20627-0008

DRILLERS' LOG

J. A. ALLISON  
No. 1 Haberman  
C S/2 SW, Sec. 24-18-18  
Rush Co., Kansas

Commenced: 3-28-77  
Completed: 4-7-77

Surface Casing: 1104.26'  
of 8-5/8", cemented  
w/300 sacks of 60-40 Posmix,  
305 sacks of common cement,  
3%cc, 2% gel  
4/2/77

FORMATION

DEPTH

Surface Hole	0 - 360
Shale, Sand, Red Bed	360 - 1013
Red Bed	1013 - 1109
Anhydrite	1109 - 1142
Sand & Shale	1142 - 1714
Shale w/Lime	1714 - 1949
Lime & Shale	1949 - 2500
Shale & Lime	2500 - 2730
Lime & Shale	2730 - 3625
Lime	3625 - 3718
Lime & Shale	3718 - 3737
Lime	3737 - 3800 R.T.D.

RECEIVED  
APR 18 1977  
4-18-77  
D. N. B. DRILLING, INC.  
Wichita, Kansas

I do hereby certify that the foregoing statements are true and correct to the best of my knowledge and belief.

D N B DRILLING, INC.

*James L. Donelson*  
JAMES L. DONELSON

STATE OF KANSAS: ss:

Subscribed and sworn to before me this 11th day of April, 1977.

*Ella Priess*

Ella Priess, Notary Public

