

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-165-21,573-0000

LEASE NAME Oliverious

WELL NUMBER 1

4290 Ft. from S Section Line

4290 Ft. from E Section Line

SEC. 36 TWP. 18 RGE. 18W (E) or (W)

COUNTY Rush

Date Well Completed 6-18-91

Plugging Commenced 12-31-91

Plugging Completed 12-31-91

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR R.P. Nixon Operations Inc.

ADDRESS 207 W. 12th Hays, KS 67601

PHONE# (913) 628-3834 OPERATORS LICENSE NO. 5252

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 12-31-91 (date)

by Dan Goodrow (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? _____

Producing Formation Arbuckle Depth to Top 3823' Bottom 3874 T.D. 3874

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

RECEIVED

KANSAS CORPORATION COMMISSION

Formation	Content	From	To	Size	Put In	Pulled out
		surf	1200	8 5/8"	1200	none
		surf	3870	4 1/2"	3870	2150'

1-27-92
JAN 27 1992

CONSERVATION DIVISION
WICHITA, KS

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set.
Dumped 30 gal of sand down 4 1/2" w/1 sx cement on top. Shot casing off at 2150'. Pulled 54 joints of 4 1/2" casing. Pumped down 8 5/8" w/300 # hulls mixed wth 10 sx gel. Pumped 50 sx 60/40 pozmix (6% gel) down 8 5/8" followed by 10 sx gel. Ran wiper plug down 8 5/8" w/1 sx hulls on top of plug. Pumped 150 sx 60/40 poz down casing. Max. press.: 950# S
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Jay Lan Corp License No. 5128

Address 207 West 12th Hays, KS 67601

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: R.P. Nixon Operations Inc.


STATE OF Kansas COUNTY OF Ellis, ss.

Dan A. Nixon, President (Employee of Operator) or (Operator) or above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) 207 West 12th Hays, KS 67601

SUBSCRIBED AND SWORN TO before me this 24th day of January, 19 92



[Signature]
Notary Public

My Commission Expires: 5-21-93