

15-009-03198-0000

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 North Market, Insurance Bldg.  
Wichita, Kansas

Barton County, Sec. 33 Twp. 16S Rge. (X) 11 (W)

Location as "NE/CNWSW¼" or footage from lines C S/2 NE SE

Lease Owner Gulf Oil Corporation

Lease Name Cynthia Rieman Well No. 4

Office Address 316 Union Center Bldg., Wichita 2, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date well completed 2-28 19 51

Application for plugging filed 4-7 19 59

Application for plugging approved 4-8 19 59


Plugging commenced 5-7 19 59

Plugging completed 5-11 19 59

Reason for abandonment of well or producing formation Well operating below its economic limit

If a producing well is abandoned, date of last production 5-16 19 56

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Donald Truan

Producing formation Arbuckle Depth to top 3372' Bottom 3393' Total Depth of Well 3393' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	756'	-0-
				5-1/2"	3374'	2682'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with sand from 3393' to 3360'. Dumped 5 sacks cement from 3360' to 3320'. Mudded hole to 350'. Set rock bridge at 350'. Dumped 25 sacks cement to 275'. Mudded hole to 40'. Set rock bridge at 40' and capped with 10 sacks cement.

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 14 1959  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Morgan Well Plugging Service

Address Hutchinson, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss. Thomas A. Trax (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Thomas A. Trax  
316 Union Center Bldg., Wichita 2, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 12th day of May, 19 59

My commission expires 2-4-63

Ray W. Rouser  
RAY W. ROUSER, NOTARY PUBLIC Notary Public.

PLUGGING  
FILE SEC 33 T 16 R 11 W  
BOOK PAGE 28 LINE 23

RECEIVED  
STATE CORPORATION

APR 8 1959

CONSERVATION DIVISION  
Wichita, Kansas

REIMANN NO. 4  
Cen. S/2 NE SE Sec. 33-16S-11W,  
Barton County, Kansas  
Gulf Oil Corporation

15-009-03198-000

8-5/8" O. D. Casing Cemented at 756'  
5-1/2" O. D. Casing Cemented at 3385'

Drilling Commenced 2-5-51  
Drilling Completed 2-16-51

FROM	TO	FORMATION	REMARKS
0'	275'	Clay, rock & shale	
275	740	Shale & shells	
740	745	Chalk	
745	770	Anhydrite	
770	1035	Red bed and shale	8-5/8" O. D. Casing cemented with 365 sacks bulk cement at 756'
1035	1405	Shale	
1405	1485	Shale & shells	
1485	1955	Lime	
1955	2060	Lime & shale	
2060	2440	Shale & lime	
2440	2500	Shale	
2500	2555	Lime	
2555	2720	Lime & shale	
2720	2805	Shale & lime	
2805	2895	Lime	
2895	3055	Lime & shale	
3055	3110	Lime	
3110	3255	Lime & shale	
3255	3350	Lime	
3350	3385	Shale & lime	5-1/2" O. D. Casing cemented with 100 sacks cement at 3385'

*Legend*      *was*      *Cobbles*      *ends*      *to*      *3393'*      *TD*

~~P. D.~~      ~~3385'~~

PLUGGING  
FILE SEC. 33 T. 16 R. 11W  
BOOK PAGE 28 LINE 23