

Called 2/6/84 W.S. Slawson  
1090174

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-165-21,214-0000  
NE NW NW, SEC. 36, T 18 S, R 18  
330 feet from N/EXsection line  
1010 feet from W/EXsection line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 5181  
Operator: Donald C. Slawson  
Name & Address: 200 Douglas Building  
Wichita, KS 67202  
263-3201

Lease Name Oliverius 'H' Well # 1  
County Rush  
Well Total Depth 3878 126.04 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 1224

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Slawson Drilling Company, Inc. License Number 5657

Address 200 Douglas Building, Wichita, KS 67202

Company to plug at: Hour: 8:00 pm Day: 27 Month: May Year: 19 84

Plugging proposal received from Glen Conway

(company name) Slawson (phone) 316-263-3201

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 3823' with 50 sx cement

2nd plug at 1260' with 40 sx cement

3rd plug at 660' with 40 sx cement  
solid bridge

4th plug hulls - poug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 15 sx cement

Plugging Proposal Received by R.B. Robertson  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None

Operations Completed: Hour: 8:00 pm Day: 27 Month: May Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 3823' with 50 sx cement, 2nd plug at 1260' with 40  
sx cement, 3rd plug at 660' with 40 sx cement, 4th & 5th plugs - solid bridge - hulls -  
plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with  
15 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION

JUN 01 1984  
6-1-84

Remarks: Use 60/40 Pozmix 2% gel 3% cc by Halliburton 787656  
(if additional description is necessary, use BACK of this form)

CONSERVATION DIVISION  
Wichita, Kansas

INVOICED

Signed R.B. Robertson  
(TECHNICIAN)

DATE 6-6-84

INV. NO. 1907  
5-27

JUN 19 1984

JUL 17 1984

FORM CP-2/3  
Rev. 01-84