

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-035-20717-00-00  
Spot: SWNWNW Sec/Twnshp/Rge: 19-32S-5E  
4684 feet from S Section Line, 4905 feet from E Section Line  
Lease Name: PAYNE Well #: 3  
County: COWLEY Total Vertical Depth: 2300 feet

Operator License No.: 33277  
Op Name: COOPER, ALBERT L.  
Address: PO BOX 381  
WINFIELD, KS 67156

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2295		75 SX
SURF	8.625	150		150 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/23/2012 8:00 AM  
Plug Co. License No.: 33277 Plug Co. Name: COOPER, ALBERT L.  
Proposal Rcvd. from: ALBERT L. COOPER Company: COOPER SERVICE Phone: (316) 204-0072

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL  
Date/Time Plugging Completed: 08/23/2012 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

4-23-2012, RIH ON WIRELINE SET PLUG @ 2255', SANDED BACK ON TOP OF PLUG @ 2135'. DUMP BAILED 5 SXS CEMENT ON TOP. 8-22-2012, RIH ON WIRELINE SHOT SQUEEZE HOLES 300'-301'. 8-23-2012, RIH W/TBG @ 300', COPELAND ACID SERVICE ESTABLISHED CIRCULATION AND MIXED & PUMPED 155 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 5:00 PM 8-23-2012. COPELAND ACID CEMENT TICKET #38060. 3-15-2013, (TOP WELL BACK TO SURFACE) RIH ON WIRELINE SHOT SQUEEZE HOLES @ 134'-135'. RIH W/TBG @ 135', COPELAND ACID MIXED & PUMPED 35 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. CEMENT TICKET #41815.

Perfs:

Top	Bot	Thru	Comments
2270	2275		CSG

RECEIVED  
KANSAS CORPORATION COMMISSION  
**APR 17 2013**  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: COMPLIANCE / 10 YR RULE/ DENIED TA

Plugged through: TBG

District: 02

Signed

DUANE KRUEGER  
4/26/13  
(TECHNICIAN)