

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-035-00422-00-01
Spot: NESEENENW Sec/Twnshp/Rge: 2-35S-3E
4316 feet from S Section Line, 2837 feet from E Section Line
Lease Name: MARSHALL Well #: 1
County: COWLEY Total Vertical Depth: 2107 feet

Operator License No.: 30253
Op Name: CYCLONE PETROLEUM, INCORPORAT
Address: 1030 W. MAIN
JENKS, OK 74037

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2050		200 SX
PROD	4.5	2107		
SURF	8.625	140		100 SX

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 04/05/2013 8:00 AM
Plug Co. License No.: 33556 Plug Co. Name: DRAKE EXPLORATION, LLC
Proposal Rcvd. from: DARREN BROYLES Company: DRAKE EXPLORATION Phone: (620) 986-5583

Proposed Plugging Method: AS PER KCC RULES & REGS/ SAND 50' ABOVE PERFS W/5 SXS, PERFORATE @ 350', CIRCULATE TO SURFACE.

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL
Date/Time Plugging Completed: 04/05/2013 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH ON WIRELINE SET 4-1/2" CIBP @ 1820', DUMP BAILED 4 SXS CEMENT ON TOP. PRESSURED CASING, HELD OK. RIH ON WIRELINE, SHOT SQUEEZE HOLES 360'-362' (4 HOLES). CONSOLIDATED OIL WELL SERVICES SWEDGED INTO 4-1/2" CASING, MIXED & PUMPED 135 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 5:00 PM 4-5 2013. CEMENT TICKET #38571. 4-9-2013, TAGGED PLUG @ SURFACE, CUT CASING 4' BELOW SURFACE.

Perfs:

Top	Bot	Thru	Comments
1862	1866	CSG	

RECEIVED
KANSAS CORPORATION COMMISSION

APR 17 2013

CONSERVATION DIVISION
WICHITA, KS

Remarks: COMPLAINCE/ LANDOWNER COMPLAINT

Plugged through: TBG

District: 02

Signed

DUANE KRUEGER
4/25/13
(TECHNICIAN)

12