

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-049-00043-00-00
Spot: SEWNESW Sec/Twnshp/Rge: 10-31S-8E
2268 feet from S Section Line, 3585 feet from E Section Line
Lease Name: BARNARD Well #: 1
County: ELK Total Vertical Depth: 1982 feet

Operator License No.: 8736
Op Name: DIXON, JAMES DAVID
Address: 1214 CYCLONE
MOLINE, KS 67353

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	1976		75 SX
SURF	8.625	60		50 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/18/2013 12:00 AM
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.
Proposal Rcvd. from: JAMES DIXON Company: _____ Phone: (620) 647-3317

Proposed Plugging Method: 1" to bottom, w/gel in hole, spot 10 sacks (which is 100ft plug), pull up 1000 ft, 5 sacks cement (50ft plug), pull up 550 and cement to surface

Plugging Proposal Received By: DUANE SIMS Witness Type: PARTIAL
Date/Time Plugging Completed: 03/19/2013 10:00 AM KCC Agent: DUANE SIMS

Actual Plugging Report:

Ran 1" to TD and spotted 15 sack plug. Pulled 1" and perforated casing at 1000' and 550'. Next day ran back into 1000' and spotted 15 sack plug. Pulled up to 550' and circulated cement to surface inside and outside of casing. Pulled 1" and topped well off. A total of 150 sacks of cement were used to plug this well.

Perfs:

Remarks:

Plugged through: TBG

District: 03

Signed *Duane Sims*
4/26/13 (TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION

Form CP-2/3

APR 18 2013

CONSERVATION DIVISION
WICHITA, KS

RECEIVED
APR 10 2013
KCC Chanute Dist. #3

DS