

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-25566-00-01  
Spot: SESENWSE Sec/Twnshp/Rge: 4-13S-19W  
1584 feet from S Section Line, 1324 feet from E Section Line  
Lease Name: KRUETZER B Well #: 1  
County: ELLIS Total Vertical Depth: 3856 feet

Operator License No.: 6009  
Op Name: DOUBLE EAGLE EXPLORATION, INC.  
Address: 800 W 47TH ST STE 318  
KANSAS CITY, MO 64112

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3855		
SURF	8.625	257		

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/15/2013 2:00 PM  
Plug Co. License No.: 31627 Plug Co. Name: WHITETAIL CRUDE, INC  
Proposal Rcvd. from: PRESTON DREILING Company: DOUBLE EAGLE EXPLORATION I Phone: (785) 639-2099

Proposed Plugging Method: Ordered 250 sx 60/40 pozmix 4% gel cement w/500 # hulls and 11 sx gel.  
Perforations 3514'-3805'  
PC 1550' w/290 sx

GPS: 38.94785 -099.43289  
1559' FSL 1274' FEL SW SW NE SE

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 04/15/2013 5:20 PM KCC Agent: PAT STAAB

**Actual Plugging Report:**

**Perfs:**

Whitetail Crude ran in hole with tubing to 3500'. Allied rigged to tubing and pumped 11 sx gel followed by 50 sx cement w/50 # hulls mixed in.  
Pulled tubing to 1540'. Allied rigged to tubing and mixed and pumped 110 sx 60/40 poz w/100 # hulls to circulate cement to surface.  
Pulled tubing. Topped off 4 1/2" casing with 20 sx cement. Hole standing full.  
Rigged to 8 5/8" casing and pumped 30 sx to pressure with 150 psi. Shut in pressure 150 psi.

Remarks: ALLIED CEMENTING CO TICKET # 56895

Plugged through: TBG

District: 04

Signed  (TECHNICIAN)

4/26/13

CM

RECEIVED  
KANSAS CORPORATION COMMISSION

APR 24 2013

CONSERVATION DIVISION  
WICHITA, KS

APR 18 2013