

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-047-21617-00-00  
Spot: SENWSENE Sec/Twnshp/Rge: 6-24S-19W  
1883 feet from N Section Line, 860 feet from E Section Line  
Lease Name: BORNHOLDT Well #: 1  
County: EDWARDS Total Vertical Depth: 5103 feet

Operator License No.: 3532

| String | Size  | Depth (ft) | Pulled (ft) | Comment         |
|--------|-------|------------|-------------|-----------------|
| SURF   | 8.625 | 395        |             | WITH 250 SX CMT |

Op Name: CMX, INC.

Address: 1700 N WATERFRONT PKWY BLDG 300  
WICHITA, KS 67206

K  
M  
C

Well Type: DH

UIC Docket No:

Date/Time to Plug: 04/04/2013 4:15 PM

Plug Co. License No.: 5929

Plug Co. Name: DUKE DRILLING CO., INC.

Proposal Rcvd. from: GALEN ROACH

Company: DUKE DRILLING CO., INC.

Phone: (316) 267-1331

Proposed Plugging Method: 1ST PLUG AT 4970' WITH 50 SX CMT. 2ND PLUG AT 1340' WITH 50 SX CMT. 3RD PLUG AT 720' WITH 50 SX CMT. 4TH PLUG AT 420' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN

Witness Type: NONE

Date/Time Plugging Completed: 04/04/2013 6:15 PM

KCC Agent: ERIC MACLAREN

Actual Plugging Report:

Perfs:

1ST PLUG AT 4970' WITH 50 SX CMT. 2ND PLUG AT 1340' WITH 50 SX CMT. 3RD PLUG AT 720' WITH 50 SX CMT. 4TH PLUG AT 420' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Remarks: USED 60/40 POZMXIX 4% GEL BY ALLIED.

Plugged through: DP

RECEIVED  
KANSAS CORPORATION COMMISSION

APR 15 2013

CONSERVATION DIVISION  
WICHITA, KS

District: 01

Signed

[Signature]  
4/24/13 (TECHNICIAN)

RECEIVED

APR - 8 2013

KCC DODGE CITY

Form CP-2/3

AMZ