

TO:
 STATE CORPORATION COMMISSION
 CONSERVATION DIVISION - PLUGGING
 130 SOUTH MARKET, SUITE 2078
 WICHITA, KANSAS 67202

API Well Number: 15-081-21339-00-01
 Spot: NWNESE Sec/Twnshp/Rge: 24-27S-34W
1221 feet from S Section Line, 1955 feet from E Section Line
 Lease Name: FREY MORROW UNIT Well #: 203 W
 County: HASKELL Total Vertical Depth: 5400 feet

Operator License No.: 5447
 Op Name: OXY USA INC.
 Address: 5 E GREENWAY PLZ PO BOX 27570
HOUSTON, TX 77227

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4057		WITH 2 SX CMT
CIBP		4224		WITH 2 SX CMT
CIBP		5010		
CIBP		5108		
PC		3185		WITH 85 SX CMT
PROD	5.5	5388	1937	335 SX
SURF	8.625	1764		WITH 425 SX CMT

Well Type: EOR UIC Docket No: E28031.1 Date/Time to Plug: 02/13/2013 2:00 PM
 Plug Co. License No.: 32833 Plug Co. Name: SARGENT LILLARD CASING PULLING, INC.
 Proposal Rcvd. from: JOHN SCHOOLCRAFT Company: SARGENT LILLARD CASING PULL Phone: (580) 254-1881

Proposed Plugging Method: SET CIBP @ 4224' WITH 2 SX CMT. CIBP @ 4057' WITH 2 SX CMT. PLUG AT 1865' WITH 80 SX CMT. PLUG AT 850' WITH 40 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: KENNY SULLIVAN WitnessType: COMPLETE (100%)
 Date/Time Plugging Completed: 02/13/2013 5:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 5010'. CIBP @ 4224' WITH 2 SX CMT. CIBP @ 4057' WITH 2 SX CMT. 1ST PLUG AT 1865' WITH 80 SX CMT. 2ND PLUG AT 840' WITH 40 SX CMT. 3RD PLUG AT 40'-0' WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5136	5140		
5112	5116		
5086	5090		
4294	4300		
4274	4285		
4192	4204		
4128	4162		
4107	4118		

RECEIVED
 MAR 08 2013
 KCC WICHITA

Remarks: **COMPLIANCE ISSUE: NOV MIT LTR** USED COMMON CEMENT BY SARGENT LILLARD.

Plugged through: CSG

District: 01

RECEIVED

MAR - 4 2013

KCC DODGE CITY

Signed

[Handwritten Signature]
 cc to me 3/11/13
 3/13/13

(TECHNICIAN)

[Handwritten mark]