

15-165-00076-0000

KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

TO:  
J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

MAY 16 1961  
5-16-61  
CONSERVATION DIVISION  
Wichita, Kansas

File No. \_\_\_\_\_ County: Rush

Location: SE NW NE Sec. 2 Twp. 19 Rge. 17 (E) \_\_\_\_\_ (W) \_\_\_\_\_

Name of Field: \_\_\_\_\_ Total Depth: 3908

I have this date completed supervision of plugging of:

Lease Name: Pechanec Well No. 1

Operator's Full Name: Skelly Oil Co

Complete Address: Box 1650 Tulsa, Oklahoma

Plugging Contractor Ace Pipe Pulling

Address: Great Bend, Kans License No. 2

Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereafter indicated: \_\_\_\_\_

Was any delay in plugging operations caused by Conservation Division Agent?

Yes \_\_\_\_\_ No

if yes how long? \_\_\_\_\_ Reason: \_\_\_\_\_

Operation Completed: Hour 1PM Day 13 Month 5 Year 61

The above well was plugged as follows:

8 5/8" 1187' circulated with cement - 5 1/2" 3908' with 125 sax cement

PB to 3855' - perforated ~~3820'~~ 3842'

Filled with sand to 3830', set 4 sax cement with dump bailer, pulled 3030'

5 1/2" - filled hole with heavy mud to 450', set 20 sax cement at 450', heavy

chunk mud to 170', set 20 sax cement at 170', heavy chunk mud to 35', set

bridge and cement to bottom cellar.

Signed: [Signature]  
Conservation Division Agent

Reviewed: [Signature]  
Field Supervisor

Remarks:

INVOICED

DATE 5/19/61

INV. NO. 3144-W