

15-165-30014-0000

KANSAS

Form CP-3
Rev. 6-26-62

K
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

MAY 12 1967
5-12-67
CONSERVATION DIVISION
WICHITA, KANSAS

Operator's Full Name Hellar Drilling Company

Complete Address: 1014 Union Center Wichita, Kansas

Lease Name Felder "A" Well No. 1

Location SE SE SE Sec. 19 Twp. 18 Rge. 19 (E) (W) X

County Rush Total Depth 3968

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling

Address: Box 405 Chase, Kansas License No. 436

Operation Completed: Hour 2 P Day 10 Month 5 Year 1967

The Above well was plugged as follows:

Total Depth 3968' 8 5/8 csg set at 1010' cwc 575 sc.

4 1/2 csg set at 3967' cw 300 sc cement.

Perf. (3956-62) Filled with sand to 3950' and dumped 4 sc cement with dump bailer.

Recov. 1800' of 4 1/2 csg.

Squeezed 8 5/8 csg. with 30 sc gel mud and 80 sc cement. Shutin pres. 250 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo P. Massey
Well Plugging Supervisor

DATE 5/12/67
INV. NO. 5210-U