

R

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 133-31

LOCATION SW of SW $\frac{1}{4}$

SEC. 24 TWP. 19 RGE. 16

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 2 Lease G. C. Brock

Operator *FLYNN* ~~Flynn~~ Oil Company Address 813 Tompson Bldg., Tulsa, Okla.

Field _____ County Rush

Total Depth 3538 Feet.

(Describe briefly the manner in which the well was plugged)

The hole was plugged back 3538' to 3500' cement, then mud to bridge
at 975'. Cement to 896'. Mud to 300'. Cement 300' to cellar base.
Then 150 sacks cement, 4 sacks A Jell between 15" and 12 $\frac{1}{2}$ " pipe.
Pressure 250 pounds. Total cement used 316 sacks, 8 sacks A Jell.
952' of 12 $\frac{1}{2}$ " and 320' of 15" pipe cemented and left in the hole.

Recheck 9-19-47 OK

Recheck 10-5-47 OK

" " 10-14-47 *JK*

H. W. K...
District Conservation Agent

Date Sept. 17-47

PLUGGING
FILE SEC 24 T 18 R 16W
133-31

