



DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. 35-10

LOCATION Fleagle C SW 1/4

SEC. 13 TWP. 21 RGE. 34W

Dry Hole _____ Abandoned Oil Well _____ Abandoned Gas Well X

I have this date completed supervision of plugging of:

Well No. 1 Lease Fleagle Gas Unit

Operator Petroleum Inc. Address 311 East Third Wichita

Field Hugoton County Finney

Total Depth 2615' Feet.

Plugging Contractor Morgan Well Plugging Service

Plugging Contractor's License No. 43

Address Hutchinson Kansas
(Describe briefly the manner in which the well was plugged)

Well was killed with water. Ran chat to 2540'. 5 sacks cement dumped
then heavy mud to 250'. Put in rock and dumped 20 sacks cement.
Heavy mud to 35' and dumped 10 sacks cement. Cut pipe off 4' below
surface and capped. 2-10-56.

RECEIVED
STATE CORPORATION COMMISSION
FEB 20 1956
CONSERVATION DIVISION
Wichita, Kansas

Gordon D Farr
District Conservation Agent

Date 2-10-56

PLUGGING
FILE SEC. 13 T. 21 R. 34W
BOOK PAGE 35 LINE 10