

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-077-21,156 -00-00

LEASE NAME Chevroux

WELL NUMBER 1

4215 Ft. from S Section Line

1240 Ft. from E Section Line

SEC. 33 TWP. 31S RGE. 5 ~~06R30X~~ (W)

COUNTY Harper

Date Well Completed 8-6-87

Plugging Commenced 8-7-87

Plugging Completed 8-7-87

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR White Oilfield Supply, Inc.

ADDRESS 906 S. Iowa, Pratt, KS 67124

PHONE#(316) 672-7130 OPERATORS LICENSE NO. 8709

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify? District 2 John Sanders

Is ACO-1 filed? No If not, is well log attached? No

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4370

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	260	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Pump mud to 675' set 1st plug from 675' to 535' with 35 sx; pump mud to 310' set 2nd plug from 310' to 170' with 35 sx; pump mud to 60' set 3rd plug from 60' to surface with 25 sx; pump 10 sx in bathole, and 10 sx in mousehole. All cement 60/40 posmix, 2% gel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Abercrombie Drilling, Inc. License No. 5422

Address 801 Union Center, Wichita, KS 67202


STATE OF Kansas COUNTY OF Sedgwick, ss.

Jack K. Wharton (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jack K. Wharton

(Address) 801 Union Center, Wichita, KS 67202

SUBSCRIBED AND SWORN TO before me this 12th day of August, 19 87



Janet A. Stuck
 Notary Public

Commission Expires: December 29, 1990

AUG 13 1987
 08-13-1987 Form CP-4
 Revised 07-86
 Wichita, Kansas