

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Building  
 Wichita, Kansas 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

API NUMBER 15,165-20,968-00-00

LEASE NAME Horst-Hanken

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

WELL NUMBER #1

2310 Ft. from S Section Line

2970 Ft. from E Section Line

SEC. 1 TWP. 19 RGE. 16 (E) or (W)

COUNTY Rush

Date Well Completed \_\_\_\_\_

Plugging Commenced 10-28-89

Plugging Completed 11-15-89

LEASE OPERATOR Jeff Gilmore

ADDRESS 1630 Cherokee, Great Bend, Ks. 67530

PHONE# (316-792-4751) OPERATORS LICENSE NO. 30225

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on October 30, 1989 (date)

by Richard Lacey & Duane Rankin (KCC District Agent's Name).

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? With application

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 3725'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	1062'	None
				4-1/2"	3722'	2,680.60'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.  
 Dumped sand to 3600' & 4 sacks cement. Shot casing at 3100', 2900', and 2650'. Pulled 64 joints of 4-1/2" casing. B.J. Titan plugged well with 300# hulls, 10 sacks gel. 50 sacks cement, 10 sacks gel, 100# hulls and 150 sacks 60/40 pozmix cement with 6% gel. Maximum pressure 900 psi and shutin 550 psi.

Name of Plugging Contractor Rockhold Engineering, Inc. License No. 5111

Address Box 698, Gt. Bend, Ks. 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Jeff Gilmore

STATE OF Kansas COUNTY OF Barton, ss.

James W. Rockhold

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

RECEIVED  
 STATE CORPORATION COMMISSION  
 11-16-1989  
 NOV 16 1989

(Signature) James W. Rockhold

(Address) Box 698, Gt. Bend, Ks. 67530

SUBSCRIBED AND SWORN TO before me this 15th day of November, 1989

CONSERVATION DIVISION  
 Wichita, Kansas

Jona M. Leatherman  
 Notary Public

My Commission Expires \_\_\_\_\_

STATE NOTARY PUBLIC  
 IONA M. LEATHERMAN  
 Barton County, Kansas  
 My Appt. Exp. 9-26-91