

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-165-20,617-A00-01

LEASE NAME Horst-Hanken

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER#2

330 Ft. from S Section Line

3630 Ft. from E Section Line

SEC. 1 TWP. 19 RGE. 16 (E) or (W)

COUNTY Rush

Date Well Completed _____

Plugging Commenced 11-6-89

Plugging Completed 11-15-89

LEASE OPERATOR Jeff Gilmore

ADDRESS 1630 Cherokee, Great Bend, Ks. 67530

PHONE# (316)-792-4751 OPERATORS LICENSE NO. 30225

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on October 30, 1989 (date)

by Duane Rankin (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, Is well log attached? With application

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3692'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	1054'	None
				4-1/2"	3691'	2,229.75'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set. Dumped sand to 3580' and 4 sacks cement. Shot casin at 2900', 2650', 2440' & 2200'. Pulled 54 joints of 4-1/2" casing. B.J. Titan plugged well with 350# hulls, 10 sacks gel, 50 sacks cement, 10 sacks gel, 50# hulls, released plug and pumped 150 sacks 60/40 pozmix cement with 6% gel. Maximum pressure was 1000 psi and shutin 750 psi.

Name of Plugging Contractor Rockhold Engineering, Inc. License No. 5111

Address Box 698, Gt. Bend, Ks. 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Jeff Gilmore

STATE OF Kansas COUNTY OF Barton, ss.

James W. Rockhold (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so I swear before God.

(Signature) James W. Rockhold

(Address) Box 698, Gt. Bend, Ks. 67530

RECEIVED
STATE CORPORATION COMMISSION
NOV 16 1989

SUBSCRIBED AND SWORN TO before me this 15th day of November, 1989

CONSERVATION DIVISION
Wichita, Kansas

Jana M. Leatherman
Notary Public

My Commission Expires _____

JANA M. LEATHERMAN
Barton County, Kansas
My Appt. Exp. 9-26-91