

15-077-30076-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Harper County. Sec. 7 Twp. 31 Rge. (E) 5 (W)

Location as "NE/CNW/SW" or footage from lines C NW NW
SLAWSON-McCLURE-RUPP

Lease Owner _____

Lease Name Latta 'A' Well No. 1

Office Address 408 One Twenty Building, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 1-14-66

Application for plugging filed 1-14-66

Application for plugging approved 1-14-66

Plugging commenced 1-14-66

Plugging completed 1-14-66

Reason for abandonment of well or producing formation D & A

If a producing well is abandoned, date of last production 19 _____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well A. Elving, Box 248, Pratt, Kansas

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4598 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	244	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mud to 240', set in 2 sacks cement, 1/3 sack hulls, solid wood plug, cemented with 25 sacks, mud to 40', 1 sack cement, 1/3 sack hulls, solid wood plug, 1 sack cement, 2 sacks in rat hole.

RECEIVED
STATE CORPORATION COMMISSION
JAN 21 1966
01-21-1966
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Slawson Drilling Company, Inc.

Address 408 One Twenty Building, Wichita, Kansas

STATE OF Kansas COUNTY OF Sedgwick ss.
Donald C. Slawson (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) _____
408 One Twenty Building, Wichita, Ks.
(Address)

SUBSCRIBED AND SWORN to before me this 19th day of January, 1966

Ella Priess
Notary Public.

My commission expires August 25, 1968

WELL LOG

Company: DONALD C. SLAWSON
 408 One Twenty Building
 Wichita, Kansas

Farm: Latta 'A' #1
 C NW NW, Section 7-31-5W
 Harper County, Kansas

Total Depth: 4598' Elev. 1331 K.B.

Commenced: December 30, 1965
 Completed: January 14, 1966

Contractor: Slawson Drilling Co., Inc.

Casing: 8-5/8" @ 244' with 210 sacks of cement


0-8	Surface Clay
8-60	Sand & Gravel
60-70	Shale & Lime
70-1150	Shale & Shells
1150-1650	Lime & Shale
1650-3225	Shale & Lime
3225-3354	Sand
3354-3375	Shale
3375-3504	Lime & Shale
3504-3545	Lime & Chert
3545-3747	Lime
3747-3800	Lime & Shale
3800-3929	Lime
3929-4017	Lime & Shale
4017-4333	Lime
4333-4345	Chalk, Shale & Lime
4345-4385	Lime & Shale Chalk
4385-4432	Lime Chalkey
4432-4480	Lime & Chalk
4480-4570	Shale
4570-4598	Sand

STATE OF KANSAS)
)SS:
 COUNTY OF SEDGWICK)

I, Donald C. Slawson, of the Slawson Drilling Company, Inc., upon oath state that the above and foregoing is a true and correct copy of the log of the Latta 'A' #1 well.


 DONALD C. SLAWSON

Subscribed and sworn to before me this 19th day of January, 1966.


 Ella Priess, Notary Public

My Commission Expires:
 August 25, 1968

RECEIVED
 STATE COMMISSIONER
 JAN 21 1966
 01-21-1966
 CONSERVATION DIVISION
 Wichita, Kansas