

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 077-21,118-00-00

LEASE NAME Latta

WELL NUMBER No. 1

3190 Ft. from S Section Line

4950 Ft. from E Section Line

SEC. 7 TWP. 31S RGE. 5 ~~WEST~~ (W)

COUNTY Harper

Date Well Completed P&A 12/29/85

Plugging Commenced 12/29/85

Plugging Completed 12/29/85

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Sohio Petroleum Company

ADDRESS 50 Penn Place, Suite 1100, Okla. City, OK 73118

PHONE# (405) 848-7571 OPERATORS LICENSE NO. 6854

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? District 2

Is ACO-1 filed? no If not, is well log attached? yes

Producing Formation NA Depth to Top NA Bottom NA T.D. 4666'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From Surface	To	Size	Put in	Pulled out
			850'	8-5/8"	850'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
RIH with 4 1/2" open ended drill pipe to 900' - set Plug #1 - mixed 35 sx 60/40 pozmix w/2% gel.
Set Plug #2 with open ended drill pipe at 60' - mixed 25 sacks 60/40 pozmix w/2% gel. Plug #3
plugged rat hole with 10 sacks 60/40 pozmix with 2% gel. Cut off 8-5/8" casing 3' below
G.L. Weld on I.D. plate.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton Services License No. 5287

Address Box 428, Hays, Kansas

STATE OF Oklahoma COUNTY OF Oklahoma, ss.

I, John F. Sindelar, (Employee of Operator) ~~xxxxxx~~ of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters hereinafter contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) John F. Sindelar

(Address) 50 Penn Place, Suite 1100,

Okla. City, OK 73118

SUBSCRIBED AND SWORN TO before me this 6th day of January, 19 86

Cynthia L. Arnold
Notary Public

My Commission Expires: 11/19/88