


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

Sumner County, Sec. 8 Twp. 30 Rge. 1 (E) EW  
Location as "NE/CNW/SW" or footage from lines SESE NE  
Lease Owner KATHOL PETROLEUM, INC.  
Lease Name LOCKHART Well No. 1  
Office Address 900 Sutton Place, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Oil  
Date well completed 2/4/65 19  
Application for plugging filed 11/4/68 19  
Application for plugging approved 11/8/68 19  
Plugging commenced 11/6/68 19  
Plugging completed 11/11/68 19  
Reason for abandonment of well or producing formation Depleted

If a producing well is abandoned, date of last production 10/31/68 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well H. E. Hess  
Producing formation Mississippi Depth to top 3348 Bottom 3351 Total Depth of Well 3810 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Kansas City	Lime	2758	2991	8-5/8	230'	None
Mississippi	Lime	3343	3348	5-1/2	3396'	2450'
Mississippi	Dolomite	3348	3366			
Simpson	Sand	3808	3810			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Sand Back 3368' to 3325' Dump 5 sx cement  
Bail hole down to 215' Rock Bridge From 215' to 200'  
Bail hole down to 200' Dump 3 yds Redi Mix Cement to surface

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 16 1968  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Ralph Comstock Pipe Pulling Inc.  
Address 411 South Buckeye, Staffor, Kansas


STATE OF Kansas COUNTY OF Sedgwick ss.  
Homer J. Catt (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Homer J. Catt  
900 Sutton Place, Wichita, Kansas  
(Address)

Subscribed and Sworn to before me this 11th day of December, 19 68

My commission expires March 28, 1971

Betty M. Maloney  
Betty M. Maloney Notary Public.



RP

DRILLER'S LOG

FARM NAME                    Lockhart #1                    LOCATION:                    SE SE NE Sec. 8-30S-1E  
 CONTRACTOR:                SHAWVER ARMOUR, INC.                    Sumner County, Kansas  
 OWNER:                      SHAWVER ARMOUR, INC.                    ELEVATION:                1250 K. B.  
 COMMENCED:                January 23, 1965                    COMPLETED:                February 4, 1965  
 CASING RECORD:            230' 8 5/8 w/200 sacks cement  
                                   Set 5 1/2" pipe @3396 w/75 sacks cement

FORMATION:

TOPS:

Top soil, sand & Clay                    0-170  
 Anhydrite                                230  
 Anhydrite & Lime                        460  
 Lime & Shale                            710  
 Shale & Lime                            1740  
 Lime & Shale                            2411  
 Sand                                        2550  
 Shale & Lime                            2758  
 Kansas City                              2870  
 Lime                                        2992  
 Lime & Shale                            3133  
 Shale & Lime                            3276  
 Lime & Shale                            3345  
 Mississippi Lime                        3343  
 Mississippi Dolomite                    3348  
 Dolomite & Chert                        3366  
 Lime & Chert                            3430  
 Lime                                        3740  
 Kinderhook                                3746  
 Simpson Sand                            3808  
 Rotary Total Depth                      3810

Stalnaker                                2411  
 Kansas City                              2758  
 Base Kansas City                        2991  
 Cherokee                                3252  
 Mississippi Lime                        3343  
 Mississippi Dolomite                    3348  
 Kinderhook                                3741  
 Simpson                                    3805

RECEIVED  
 STATE CORPORATION COMMISSION  
 NOV 8 1968  
 CONSERVATION DIVISION  
 Wichita, Kansas

STATE OF KANSAS }  
 SEDGWICK COUNTY }    ss

I, James M. Armour, do hereby certify that the above log is a true and correct copy of the above captioned well as shown on the daily drilling reports.

SHAWVER ARMOUR, INC.

BY James M. Armour  
 James M. Armour

Subscribed and sworn to before me this 9th day of February 1965.

My commission expires December 10th, 1967

Claire Jones  
 Claire Jones    Notary Public

