

STATE OF KANSAS
STATE CORPORATION COMMISSION


~~We also are in need of a well log on this well~~

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above Section Plat

County. Sec. 27 Twp. 31 Rge. 1W 16 (W)

Location as "NE/CNW/SW" or footage from lines NW NE SE

Lease Owner Time Petroleum Company

Lease Name Voils Well No. I

Office Address 815 Union National Bldg., - Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) D&A

Date well completed 10/9/57 19

Application for plugging filed 10/9/57 19

Application for plugging approved 10/9/57 19

Plugging commenced 10/9/57 19

Plugging completed 10/9/57 19

Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eugene Graham

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3677' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled with mud to 342' pushed down Halliburton plug and 1/2 sack hulls. Put in 15 sacks cement. Mud from there to 35' Put in wood plug and 9 sacks cement. Cut off surface at 2' and filled with Cement.

RECEIVED
STATE CORPORATION COMMISSION

APR 28 1966

CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Target Drilling Company Tools

Address _____

STATE OF Kansas COUNTY OF Edgewood ss.

Employee of owner (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Max Kuttawite
815 Union National Bldg
Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 26th day of April, 1966

Josephine Warner
Notary Public.

My commission expires 9-6-69

Time Petr;

TARGET DRILLING AND
PRODUCING COMPANY, INC.
WICHITA, KANSAS
DRILLER'S WELL LOG

9

#1 Voils
Sec. 27-31S-1W, NW, NE, SE
Sumner County, Kansas
Commenced 9/20/57
Completed 10/4/57

27-31-1W

DEPTH		FORMATION	REMARKS
From	To		
0	348	Surface Hole	Ran 348' of 8 5/8" Pipe Cemented W/350 Sacks Cement
348	360	Lime	
360	600	Lime, Shale	
600	720	Lime, Shale, Red Bed	
720	800	Sand	
800	815	Shale Shells	
815	1020	Lime, Shale	
1020	1050	Shale	
1050	1070	Sand	
1070	1320	Shale, Sandy Shale	
1320	1580	Shale, Sandy Shale	
1580	1640	Shale, Lime Stks	
1640	1830	Shale, Lime Stks	
1830	1895	Lime	
1895	2105	Shale, Lime	
2105	2250	Shale, Lime	
2250	2420	Lime, Shale	
2420	2640	Lime, Shale	
2640	2655	Shale, Lime	
2655	2780	Sandy, Shale	
2780	2810	Lime, Shale	
2810	2900	Shale, Lime	
2900	3009	Shale	
3009	3060	Lime	
3060	3110	Lime	
3110	3170	Lime	
3170	3220	Lime	Cir. 1 Hr. @ 3207
3220	3255	Lime	
3255	3280	Shale	
3280	3301	Lime	
3301	3312	Sandy, Lime	Cir. 3/4 Hr. @ 3307 for Samples
3312	3335	Lime, Shale	
3335	3405	Lime, Shale	
3405	3465	Lime, Shale	
3465	3505	Lime, Shale	
3505	3550	Lime	
3550	3635	Shale Lime	Cir. 1 Hr. @ 3625
3635	3655	Shale, Lime	Cir. 1 1/2 Hr. @ 3647
3655	3661	Lime	
3661	3669	Core	
3669	3677	Lime	
3677	T.D.	D+4	

RECEIVED
STATE CORPORATION COMMISSION

APR 28 1966

STATE CORPORATION COMMISSION
WICHITA, KANSAS

I hereby certify the above and foregoing to be a true and correct copy of the log of #1 Voils, located in the NW, NE, SE, Sec. 27,31S,1W, Sumner County, Kansas to the best of my knowledge.

TARGET DRILLING & PRODUCING CO., INC.

By R.C. Long
Secretary

State of Kansas
County of Sedgewick

Subscribed and sworn to before me this 28th day of October, 1957.

Arthur L. Marshall
Notary Public

My Commission Expires: Sept. 19, 1959.