

15-083-20104-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Hodgeman SEC. 31 TWP. 23s RGE 21w E/W
Location as in quarters or footage from lines:
SE NE SE

Lease Owner Kaiser-Francis
Lease Name Hall F #2 Well No. _____
Office Address Box 666, Ellinwood, Ks. 67526
Character of Well (Completed as Oil, Gas or Dry Hole): _____
Date Well Completed _____
Application for plugging filed _____
Plugging commenced 12/14/82
Plugging completed 12/21/82
Reason for abandonment of well or producing formation
Depleted

Locate Well
correctly on above
Section Platt.

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Steve Durrant
Producing formation _____ Depth to top _____ bottom _____ T.D. 4587'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8	278	none
				5 1/2	4579'	3014'

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

Plugged bottom with sand to 4280', ran 5 sacks cement. Shot at 3015'.
Pulled total of 94 joints. Squeezed hole with 3 sacks hulls, 15 sacks gel,
70 sacks cement, 1 sack hulls, & 15 sacks gel. Released plug & displaced
with 150 sacks cement.

Plugging complete


(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.
R. Darrell Kelso (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
Box 347, Chase, Ks. 67524
(Address)

SUBSCRIBED AND SWORN TO before me this 23rd day of December, 19 82

My Commission expires: 

 **RECEIVED**
STATE CORPORATION COMMISSION
Notary Public.
DEC 30 1982

CONSERVATION DIVISION
Wichita, Kansas

GARRETT-JONES, INC.
WICHITA, KANSAS
DRILLERS' WELL LOG

HALL "F" #2
 SE NE SE Section 31-23S-21W
 Hodgeman County, Kansas

Commenced: November 20, 1969
 Completed: December 1, 1969

OPERATOR - Francis Oil & Gas, Inc.

DEPTH		FORMATION	REMARKS
From	To		
0	198	Clay and shale	
198	278	Sand and shale	
278	278	Shale	Ran 9 joints 8-5/8" casing, set @ 278' w/200 sacks cement.
278	743	Shale and red bed	
743	808	Anhydrite	
808	890	Shale	
890	1092	Sand	
1092	1427	Shale and red bed	
1427	1442	Anhydrite	
1442	1650	Shale and red bed	
1650	2060	Shale and shells	
2060	4031	Shale and lime	
4031	4587	Lime	
4587	TD		Ran 144 joints of 5-1/2" casing, set @ 4579' w/125 sacks cement.

I, E. E. HALL, certify this is a correct copy of the Driller's Log for the well drilled in the SE NE SE Section 31-23S-21W, Hodgeman County, Kansas, to the best of my knowledge and belief.

E. E. Hall

 E. E. HALL

STATE OF KANSAS)
) St
 COUNTY OF SEDGWICK)


Before me, hte undersigned, a Notary Public within and for said County and State, on this 2 day of January, 1970, personally appeared E. E. Hall to me personally known to be the identical person who executed the within and foregoing instrument and acknowledged to me that he executed the same as his free and voluntary act and deed for the uses and purposes therein set forth.

IN WITNESS WHEREOF, I have hereunto set my hand and official seal the day and year last above written.

My Commission Expires Feb. 1, 1972.

Barbara J. Layton

 Barbara J. Layton, Notary Public



RECEIVED
 STATE CORPORATIONS COMMISSION

OCT 06 1982

CONSERVATION DIVISION
 Wichita, Kansas