

15-165-00167-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

Rush County. Sec. 31 Twp. 18 S Rge. 20 (E) W (W)

Location as "NE/CNW%SWK" or footage from lines C SE SE SW

Lease Owner M. M. & B.

Lease Name Herring Well No. 1

Office Address

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 7-5-55 19

Application for plugging filed 7-5-55 19

Application for plugging approved 19

Plugging commenced 7-5-55 19

Plugging completed 7-5-55 19

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Horner

Producing formation Depth to top Bottom Total Depth of Well 4720 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface Casing		Surface	204'	8 5/8"		
	175 sacks cement 2% C.C. cement air.					

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Hole pumped full of heavy Rotary mud from 4720' to within 200' of surface.

Halliburton plug placed @ 200'. 1/3 sack of hulls placed on plug

20 sacks of cement mixed through Drill pipe placed on plug.

Heavy mud from 200' to 35' from base of cellar.

Halliburton plug @ 35'. 1/3 sack of hulls on plug. 10 sacks of cement to base of cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Badger Drillers Inc.

Address Tulsa, Oklahoma

STATE OF OKLAHOMA, COUNTY OF TULSA, ss.

Don E. Burkitt

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God

(Signature) [Signature]

Box 287, Tulsa 1, Oklahoma

(Address)

SUBSCRIBED AND SWORN TO before me this 21st day of July, 19 55

[Signature]

Notary Public.

My commission expires 4-13-58

24-2675-8 2-32-20M

PLUGGING  
RUSH SEC 31 T 19 R 200  
BOOK PAGE 133 LINE 2

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 17 1955  
8-19-55  
CONSERVATION DIVISION  
Wichita, Kansas

15-165-00167-0000

BADGER DRILLERS, INCORPORATED

Herring # 1  
SE SE SW Sec. 31-13S-20W  
Rush County, Kansas

Drilling Started 6-20-55  
Drilling Completed 7- 5-55  
8 5/8 Casing Cemented at 204'

<u>FROM</u>	<u>TO</u>	<u>FORMATION</u>	<u>REMARKS</u>
-0-	40'	Clay-Rock	
40'	162'	Shale	
162'	204'	Shale and Shells	Ran 10 JTS 8 5/8" O.D. Casing Set At 204' with 150 Sks. Cement
204'	530'	Shale	
530'	840'	Shale and Shells	
840'	1060'	Sand	
1060'	1270'	Red-Bed	
1270'	1390'	Shales & Red Bed	
1390'	1425'	Anhydrite	
1425'	1874'	Shale and Shells	
1874'	2175'	Shale	
2175'	2315'	Shale and Lime	
2315'	2445'	Shale	
2445'	2840'	Lime	
2840'	3499'	Shale and Lime	
3499'	3585'	Lime	
3585'	3670'	Lime and Shale	
3670'	4338'	Lime	
4338'	4415'	Chert and Lime	
4415'	4525'	Lime	
4525'	4617'	Chert and Lime	
4617'	4720'	Lime	T.D. 4720' Dry Hole

This is a certified copy of the Drillers Log as shown by the Daily Drilling Reports.

*Richard C. ...*  
BADGER DRILLERS, INC.

Subscribed and sworn to before me this day  
14th of July 1955.

RECEIVED  
STATE CORPORATION COMMISSION

AUG 13 1955  
8-13-55

PLUGGING  
FILE SEC 31 T 18 R 20W  
BOOK PAGE 133 LINE 2

*Oral ...*  
Notary Public

My commission expires 10-20-57.