


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Rush County. Sec. 28 Twp. 18S Rge. (E) 20 (W)
Location as "NE/CNW/SW" or footage from lines NE NW SE
Lease Owner Rains & Williamson Oil Co., Inc.
Lease Name Bannister Well No. 1
Office Address 1425 Wichita Plaza, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 9-1 1970
Application for plugging filed 9-1 1970
Application for plugging approved 9-1 1970
Plugging commenced 9-1 1970
Plugging completed 9-1 1970
Reason for abandonment of well or producing formation No oil or gas found
in commercial quantities.
If a producing well is abandoned, date of last production -- 19--
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey, Hays, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4230 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	250'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Set first plug @ 500' with 70 sacks; second at
240' with 20 sacks; top plug at 40' with 10 sacks,
solid bridge to surface. Plug Down at 10:00 a.m.
9-1-70.

RECEIVED
STATE CORPORATION COMMISSION
SEP 10 1970
CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor Rains & Williamson Oil Co., Inc.
Address 1425 Wichita Plaza, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Wilson Rains (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Wilson Rains Wilson Rains
1425 Wichita Plaza, Wichita, Kansas
(Address)

Subscribed and Sworn to before me this 8 day of September, 1970
Jeanine Durand
Notary Public.
My commission expires March 31, 1974

ROTARY DRILLING LOG

Operator: Rains & Williamson
Oil Co., Inc.
BANNISTER #1
NE NW SE Sec. 28-18S-20W
Rush County, Kansas

Contractor: Rains & Williamson
Oil Co., Inc.
Commenced: 8-23-70
Completed: 9-1-70
Casing: 8-5/8"/250'/175 sacks

Formations

Post Rock	75'
Shale	785'
Sand	995'
Red Bed	1374'
Anhydrite	1405'
Shale and Red Bed	1875'
Shale and Lime	2490'
Lime	2645'
Lime and Shale	3020'
Shale and Lime	3195'
Lime and Shale	3630'
Lime	4125'
Lime and Sand	4145'
Lime	4230'
Rotary Total Depth	4230'

RECEIVED
STATE CORPORATION COMMISSION
SEP 10 1970
CONSERVATION DIVISION
Wichita, Kansas

We certify the above log is
true and correct, to the best
of our knowledge and belief.

RAINS & WILLIAMSON OIL CO., INC.

William Rains

Subscribed and sworn to me, a Notary Public within and for the
State of Kansas, County of Sedgwick, this 8 day of September, 1970.

Jeanine Durand
Jeanine Durand Notary Public



My Commission Expires: 3-31-74