

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Rush County, Sec. 26 Twp. 18S Rge. 20W E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines _____


SW NW
Lease Owner KRM Petroleum Corporation
Lease Name LEROY #1-26 Well No. #1-26
Office Address Guaranty Bank Bldg, 817 17th St., Denver, CO
Character of Well (Completed as Oil, Gas or Dry Hole) 80202
Dry Hole

Date Well completed May 29 1981
Application for plugging filed May 29 1981
Application for plugging approved May 29 1981
Plugging commenced May 29 1981
Plugging completed May 29 1981

Reason for abandonment of well or producing formation _____
No commercial quantity of oil or gas encountered.
If a producing well is abandoned, date of last production _____ 19____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Marion Schmidt
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4150'
Show depth and thickness of all water, oil and gas formations.



Locate well correctly on above Section Plat

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

T.D. @ 4150'
Set 1st Plug @ 1360' with 55 sacks.
Set 2nd Plug @ 270' with 40 sacks.
Set 3rd Plug @ 40' Solid Bridge with 10 sacks.
5 sacks in rathole, 50-50 posmix, 6% gel. Cement by Halliburton.

Plug was down @ 7:40 a.m., 5/29/81.
State Plugger - Marion Schmidt.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Abercrombie Drilling, Inc.


STATE OF Kansas COUNTY OF Sedgwick, ss.
Jack L. Partridge, Vice President (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jack L. Partridge
801 Union Center, Wichita, KS 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 4th day of June, 1981

Suzanne M. Hofer
Suzanne M. Hofer Notary Public.

My commission expires 2/4/85



CONTRACTOR'S WELL LOG

OPERATOR:	KRM Petroleum Corporation
CONTRACTOR:	Abercrombie Drilling, Inc.
WELL NAME:	LEROY #1-26
LOCATION:	SW NW, Section 26-18S-20W Rush County, Kansas
SPUD DATE:	5/20/81
COMPLETION DATE:	5/29/81

0	410	Clay and Sand
410	1315	Sand and Shale
1315	1346	Anhydrite
1346	2523	Sand & Shale
2523	2707	Shale & Redbeds
2707	2918	Lime & Shale
2918	3110	Shale
3110	3800	Shale & Lime
3800	3920	Lime & Shale
3920	4108	Shale & Lime
4108	4150	Lime and Shale
	4150	Rotary Total Depth

Spud @ 5:30 p.m., 5/20/81. Cut 1020' in the last 24 hrs. Drilled 1355' of a 12 1/4" hole. Ran 32 joints of 8 5/8" - 24# casing (tally 1342') Set @ 1350', Cemented with 550 sacks of common 2% gel, 3% c.c. Cement by Halliburton did circulate. Plug down @ 5:30 a.m., 5/22/81.

T.D. @ 4150'. Set 1st Plug @ 1360' with 55 sacks, Set 2nd Plug @ 270' with 40 sacks, Set 3rd Plug @ 40' Solid Bridge with 10 sacks, 5 sacks in rathole, 50-50 posmix, 6% gel, Cement by Halliburton. State Plugger - Marion Schmidt. Plug down @ 7:40 a.m., 5/29/81.

SAMPLE TOPS:

Anhydrite 1315'
B/Anhydrite 1346'

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

Jack L. Partridge, Vice President of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the LEROY #1-26, SW NW, Section 26-18S-20W, Rush County, Kansas.

ABERCROMBIE DRILLING, INC.

BY: Jack L. Partridge
Jack L. Partridge, Vice President

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state as of this 4th day of June, 1981.

RECEIVED
STATE CORPORATION COMMISSION

JUN - 8 1981

6-8-81

Suzanne M. Hofer
Suzanne M. Hofer, Notary Public, Kansas

