

15-165-0016-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

WELL PLUGGING RECORD

NORTH

Locate well correctly on above
Section Plat

Rush County. Sec. 17 Twp. 18 Rge. (E) 20 (W)
 Location as "NE/CNW/SW" or footage from lines NW NW NW
 Lease Owner Petroleum, Inc.
 Lease Name JONES 'M' Well No. 1
 Office Address 311 East Third, Wichita, Kansas
 Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
 Date well completed September 1 19 55
 Application for plugging filed September 1 19 55
 Application for plugging approved September 1 19 55
 Plugging commenced September 1 19 55
 Plugging completed September 1 19 55
 Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Mr. W. L. Horner
 Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4605 Feet
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	257	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mudded up to 257' and set Halliburton plug

at 257'. Placed 1/3 sack of hulls on top of plug,
 cemented and displaced through drill pipe with 20 sacks cement.

Mudded up to 35' and placed second plug at 35'. Placed 1/3
 sack of hulls on top of plug. Filled hole to bottom of
 well cellar with 10 sacks cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Garvey Drilling Company
 Address R. R. #2 - Great Bend, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Karl E. Becker (employee of owner) or (~~owner~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Karl E. Becker
311 East Third, Wichita, Kansas
 (Address)

SUBSCRIBED AND SWORN TO before me this 1st day of September, 19 55

My commission expires August 8, 1959

Floria Morrison
 Notary Public.

RECEIVED
 STATE CORPORATION COMMISSION
 9-22-55
 CONSERVATION DIVISION
 Wichita, Kansas

PLUGGING
 FILE SEC 17 T 18 R 20W
 BOOK PAGE 147 LINE 37

15-165-00166-0000
WELL LOG

COMPANY **Petroleum, Inc.**

SEC. **17** T. **18** R. **20W**

FARM **JONES #1** NO. **1**


LOC. **107 107 107**
330' SW.
330' SW.

TOTAL DEPTH **1605'**

COUNTY **Rush County**

COMM. **August 18, 1955** COMP. **September 1, 1955**

CONTRACTOR **Carvey Drilling Company**



CASING **8-5/8" O 257' w/175 cas.**

ELEVATION **2133' BS**
2155' BS

PRODUCTION **D.O.A.**

FIGURES INDICATE BOTTOM OF FORMATIONS

15 Surface Sand & Clay
70 Foot Rock
257 Shale
335 Shale & Shells
380 Sand
600 Shale & Shells
710 Sand & Shale
810 Red Bed
1120 Sand & Shale streaks
1385 Shale & Shells
1430 Anhydrite
2050 Shale
2220 Shale & Lino
2445 Lino & Shale
2505 Lino
3070 Lino & Shale
3570 Lino, Shale streaks
4257 Lino
4160 Shale
4180 Sand
4833 Shale & Lino
4240 Shale
4273 Missisippian Chert & Lino
4298 Lino
4311 Missisippian Lino
4371 Cherty Dolomite & Lino
4425 Lino
4479 Lino & Chert
4512 Lino & Dolomite
4559 Lino
4572 Open
4605 Arkoside

Geological Note

Hoboken 3619 (-1131)
Zanclay 3661 (-1529)
Charoee Sands 4241 (-2006)
Missisippian Chert 4223 (-2033)
Viola 4370 (-2255)
Dugport 4510 (-2575)
Arkoside 4559 (-2618)

A.S.D. 1605'

State of KANSAS)
County of OSAGE) SS:

I, Carl E. Becker of Petroleum, Inc.
upon oath state that the above and foregoing is a true and correct copy of the log of the JONES #1 well

Subscribed and sworn to before me this 15th day of September 19 55

My Commission Expires: August 8, 1959

Gloria Mowson
NOTARY PUBLIC

PLUGGING
FILE SEC 17 T 18 R 20W
BOOK PAGE 147 LINE 37

RECEIVED
STATE CORPORATION COMMISSION
SEP 22 1955
CONSERVATION DIVISION
Wichita, Kansas