

API NUMBER 15-165-20,752

LEASE NAME Weigand

WELL NUMBER #1

2970 Ft. from S Section Line

320 Ft. from E Section Line

SEC. 3 TWP. 18 SRGE. 18W(E) or (W)

COUNTY Rush

Date Well Completed 2-14-80

Plugging Commenced 3-24-93

Plugging Completed 3-24-93

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Chief Drilling, Inc.

ADDRESS 120 S. Market, #300, Wichita, KS 67202

PHONE#(316) 262-3791 OPERATORS LICENSE NO. 5886

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 3-24-93 (date)

by Dan Goodrow (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? by original operator in 1980

Producing Formation Arbuckle Depth to Top 3837 Bottom 3842 T.D. 3842'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	1209	-0-
				5 1/2"	3837	1993

RECEIVED
STATE CORPORATION COMMISSION
APR 2 1993

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If other plugs were used, state the character of same and depth placed, from feet to feet each section.

Mixed & pumped 300# hulls, 10 sx gel followed w/250 sx
60/40 pozmix w/8% gel down 8 5/8" casing to plug well.
Max PSI 700# shut-in PSI 500#

Name of Plugging Contractor Chief Drilling, Inc. License No. 5886

Address 120 S. Market, #300, Wichita, Kansas 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Chief Drilling, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss. Conservation Division

Douglas W. Thimesch (Employee of Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) 120 S. Market, #300

Wichita, Kansas 67202

AND SWORN TO before me this 1st day of April, 19 93



Betty M. Abbott
Notary Public

My Commission Expires: January 22, 1995

USE ONLY ONE SIDE OF EACH FORM