

15-165-20193-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

Form CP-4

WELL PLUGGING RECORD

NORTH

Locate well correctly on above
Section Plat

Rush County, Sec. 3 Twp. 18 S Rge. 18 (E) W (W)
Location as "NE/CNWXSW" or footage from lines SW SW NW
Lease Owner Birmingham-Bartlett Drilling Company
Lease Name Erbes "A" Well No. 1
Office Address 300 Kaufman Building, Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) D & A
Date well completed October 29, 1968
Application for plugging filed October 29, 1968
Application for plugging approved October 29, 1968
Plugging commenced October 29, 1968
Plugging completed October 29, 1968
Reason for abandonment of well or producing formation D & A

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Lee F. Massey
Producing formation Depth to top Bottom Total Depth of Well 3843 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS					CASING RECORD	
FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	1226'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mud to 500', 1 sx hulls
25 sx cement thru' D.P.
mud to 40', 1 sx hulls, 11 sx
cement. Completed 11:30 P.M.

RECEIVED
STATE CORPORATION COMMISSION
NOV 6 1968
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Red Tiger Drilling Company
Address 1720 Wichita Plaza Building, Wichita, Kansas 67202

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Norman E. Klein (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Norman E. Klein
1720 Wichita Plaza, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN to before me this 5th day of November, 1968

My commission expires My Commission Expires Aug. 27, 1969
Donald A. Gore Notary Public.

15-165-20193-0000

DRILLERS LOG

No. 1 Erbes "A"

CASING RECORD:	COMPANY:	Birmingham-Bartlett	DESCRIPTION:
8 5/8" @ 1234'	CONTRACTOR:	Red Tiger Drilling Co.	SW SW NW
w/375 sx cement	COMMENCED:	October 21, 1968	3-18S-18W
	COMPLETED:	October 29, 1968	Rush County,
			Kansas
TOTAL DEPTH: 3843'			ELEVATION:

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Shale	0	100	
Shale and Sand Streaks	100	585	
Shale	585	616	
Sand	616	880	
Shale	880	1227	
Anhydrite	1227	1260	
Shale	1260	1620	
Shale and Lime	1620	3160	
Lime	3160	3843	

RECEIVED
STATE CORPORATION COMMISSION
NOV 6 1968
CONSERVATION DIVISION
Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

Norman E. Klein
Norman E. Klein

Subscribed and sworn to before me this 5th day of November, 1968.

Donald A. Gore
Notary Public

My Commission Expires:

My Commission Expires Aug. 27, 1969