

2 040099

API NUMBER 15-07721010-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION NE/SE/SW, SEC. 26, T. 31 S, R. 5 W
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

_____ feet from N/S section line
_____ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License 5020

Lease Name Hiebert Well # 1-26

Operator: Rine Exploration

County Harper

Name & Address 300 W Douglas

Well Total Depth 4815 ^{156.49} feet

Sub. 600

Conductor Pipe: Size _____ feet

Wichita Ks 67202

Surface Casing: Size 8 5/8 feet 358 ²⁸⁰

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A

Other well as hereinafter indicated _____

Plugging Contractor Beredco Inc License Number 5147

Address 401 E Douglas Sub 402 Wichita Ks 67202

Company to plug at: Hour: 2100 Day: 9 Month: 7 Year: 19 84

Plugging proposal received from Gary Marshall

(company name) Beredco Inc (phone) _____

were: 40 SX 4400'

35 SX 950'

35 SX 400

25 SX 60

10 SX RH

10 SX MH Plugging Proposal Received by Don Thompson (TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
JUL 17 1984
07-17-1984
CONSERVATION DIVISION
Wichita, Kansas

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 0345 Day: 10 Month: 7 Year: 19 84

ACTUAL PLUGGING REPORT Filled hole with Mud, ran drill Pipe

to 4400' and spot 40 sacks of cement on top of Arbach.

Pulled Pipe to 930' and spotted 35 sacks of cement

Pulled pipe to 403 and spotted 35 sacks of cement.

Pulled pipe from hole, set a bridge at 20' and

spotted 25 sacks of cement. Circulated 10 sacks of

Remarks: cement in Rat hole and 10 sacks in the mouse

(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 7-30-84 observe this plugging.

Signed Stallin Gun (TECHNICIAN)

INV. NO. 2262
7-10