

2 040216

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-077-2112-00-00
01NW/SE SEC. 20, T. 31 S. R. 5 @ 10
1980 feet from N @ section line
1980 feet from W @ section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 16785
Operator: Robert Schulin
Name & Address 1776 Lincoln St #811
Denver Colorado
80203

Lease Name Allison Well # 10-20
County Harper 153.73
Well Total Depth 4730 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 338

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Red Tiger Drlg. License Number 5302

Address Wichita Ks.

Company to plug at: Hour: _____ Day: _____ Month: _____ Year: 19 _____

Plugging proposal received from Ross Crawford

(company name) Red Tiger Drlg. (phone) _____

were: 35sx 630, 35sx 380, 25sx 60', 10sx RH.

Plugging Proposal Received by Stan Marcotte
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 0315 Day: 5 Month: 11 Year: 19 85

ACTUAL PLUGGING REPORT Drill Pipe was run into the hole to 630' where
35 sk of cement was spotted to cover the Annular Space. The pipe
was pulled to 380' or 50' below the surface pipe, and another
35 sk of cement was spotted. 1 sk of shells and a Wood &
Rubber plug was pulled to 60' and 25 sk of cement was
circulated in the hole. 10 sk of cement was circulated in the

Remarks: Rat hole By Sun Cementing # 283799 60/40 6/10 gel
(If additional description is necessary, use BACK of this form.)

INVOICED

(If no) observe this plugging.

Signed Stan Marcotte
(TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
NOV 12 1985
11-12-1985
CONFIRMATION 2 WASHINGTON
VRama, Okla. 67202

DATE 11-13-85
INV. NO. 11010

WK