

2-26

2-100694

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
200 Colorado Derby Building
Wichita, Kansas 67202

API NUMBER: 15-077-21,237-00-00

NW SE NW, SECTION 33 TOWNSHIP 31 RANGE 5W

OPERATOR LICENSE # 5047 3630 FEET FROM S SECTION LINE
3630 FEET FROM E SECTION LINE

OPERATOR Rupe Oil Company, Inc.
NAME & Box 2273
ADDRESS Wichita, KS 67201

LEASE NAME: Ioerger #1
COUNTY: Harper 117.97
WELL TOTAL DEPTH: 3630'

CONDUCTOR PIPE: _____
SURFACE CASING: 8-5/8" @ 225'

ABANDONED OIL WELL _____ GAS WELL _____ INPUT WELL _____ SLD _____ D&A X

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: Lobo Drilling Company
ADDRESS: Box 877, Great Bend, KS 67530 LICENSE: 5864

COMPANY TO PLUG AT: HOUR: 7:00p DAY: 26 MONTH: 2 YR: 1991

PLUGGING PROPOSAL RECEIVED FROM: Erwin Neighbors
COMPANY NAME: Rupe Oil Company PHONE: 316-262-3748

WERE: 35 sx 950' - 35 sx 650' - 35 sx 275' - 25 sx 60' - 10
sx R.H. - 10 sx MH

PLUGGING PROPOSAL RECEIVED BY: Ralph Tittel

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL () PART () NONE (X)

COMPLETED: HOUR: 8:00p DAY: 26 MONTH: 2 YEAR: 1991

ACTUAL PLUGGING REPORT:
Filled hole w/mud - pulled drl pipe to 950' - spotted
35 sx cmt - pulled pipe to 650' & spotted 35 sx cmt -
pulled pipe to 275' & spotted 35 sx cmt - pulled pipe
to 60' - circ to surf w/25 sx cmt - put 10 sx in rat
hole and 10 sx in mouse hole.

REMARKS: Howco #042017 Cl "A" 2% gel

I DID NOT OBSERVE THIS PLUGGING.

INVOICED

John L. Sanders
J. L. Sanders (AGENT)

DATE 4-5-91 APR 4 1991

FORM CP-2/3
REV. 3/90

INV. NO. 31345 04-04-1991
CONSERVATION DIVISION
Wichita, Kansas