

1 120341

11-15

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-165-20,968-00-00  
NE NE SW, SEC. 1, T 19 S, R 16 ~~WXX~~  
2310 feet from S section line  
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 30225  
Operator: Jeff Gilmore  
Name & Address 1630 Cherokee  
Great Bend, KS 67530

Lease Name Horst-Hanken Well # 1  
County Rush 121.06  
Well Total Depth 3725 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 1062

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Rockhold Engineering, Inc. License Number 5111  
Address Box 698, Great Bend, KS 67530

Company to plug at: Hour: 10:30 a.m. Day: 15 Month: 11 Year: 19 89

Plugging proposal received from Jim Rockhold  
(company name) Rockhold Engineering, Inc. (phone) 316-792-2506  
were: 4 1/2" at 3722' Perfs at 3658-62'

1st plug sand back to 3600' and dump 4 sx cement on top of sand through bailer,  
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"  
wiper plug and pump 150 sx cement.

RECEIVED  
STATE CORPORATION COMMISSIONS

Plugging Proposal Received by Steve Pfeifer NOV 20 1989  
(TECHNICIAN) 11-201989

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_  
Wichita, Kansas

Operations Completed: Hour: 12:20 p.m. Day: 15 Month: 11 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug sanded 4 1/2" casing back to 3600' and dumped 4 sx cement  
on top of sand through bailer,  
2nd plug pumped into 8 5/8" surface casing with 350 lbs. hulls, 10 sx gel, 50 sx cement,  
10 sx gel, 50 lbs. hulls, released 8 5/8" wiper plug and pumped 150 sx cement.  
Pumping pressure 0-700 psi and shut in 550 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 2680' of 4 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 12-4-89

INV. NO. 26555

Signed Steve Pfeifer  
(TECHNICIAN)