

8-30

2-040568 RECEIVED  
STATE CORPORATION COMMISSION

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - Plugging Section  
200 Colorado Derby Building  
Wichita, Kansas 67202

SEP 7 1990  
09-13-90  
CONSERVATION DIVISION  
Wichita, Kansas

API NUMBER: 15-191-21676-0000

SW NW SW, SECTION 27 TOWNSHIP 31 RANGE 1W

OPERATOR LICENSE # 9987 1650 FEET FROM S SECTION LINE  
4950 FEET FROM E SECTION LINE

OPERATOR M&B Well Service  
NAME & P. O. Box 216  
ADDRESS Wellington, KS 67152

LEASE NAME: Martin #2

COUNTY: Sumner  
WELL TOTAL DEPTH: 3733' 121.32

PIPE: " @  
SURFACE CASING: 8-5/8" @ 464'

ABANDONED OIL WELL X GAS WELL \_\_\_\_\_ INPUT WELL \_\_\_\_\_ SMD \_\_\_\_\_ D&A \_\_\_\_\_

OTHER WELL AS HEREINAFTER INDICATED: \_\_\_\_\_

PLUGGING CONTRACTOR: B&S Well Service  
ADDRESS: Winfield, KS LICENSE: 6013

COMPANY TO PLUG AT: HOUR: \_\_\_\_\_ DAY: \_\_\_\_\_ MONTH: \_\_\_\_\_ YR: 1990

PLUGGING PROPOSAL RECEIVED FROM: Bobby Suttle  
COMPANY NAME: B&S Well Service PHONE: \_\_\_\_\_

WERE: 5-1/2" @ 3800' - perfs 3658-3670' - sand to 3600' & 5  
sx - recover pipe - 40 sx 514' gel spacer - circ 60' to  
0'.

PLUGGING PROPOSAL RECEIVED BY: Steve Van Gieson

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL (     ) PART ( X ) NONE (     )

COMPLETED: HOUR: 11:30 DAY: 30 MONTH: 8 YEAR: 1990

ACTUAL PLUGGING REPORT:  
The perfs were covered w/chat to 3600' & capped w/5 sx  
cmt thru dump bailer - 5-1/2" recovered from 2501' &  
pulled to 514' - hole circ w/gel & 40 sx plug spotted  
and displaced w/gel - casing pulled to 60' & circ to  
surf.

REMARKS: Howco #986369 60/40 2%

I DID OBSERVE THIS PLUGGING.

Steve Van Gieson  
Steve Van Gieson (AGENT)

INVOICED

DATE: 9-17-90

INV. NO. 29339

8-30

FORM CP-2/3  
REV. 3/90