

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-083-00134-0000

SE/4, Sec. 31, T 23 S, R 21 W/4
(C-SE-SE) feet from N/S section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6568

_____ feet from W/E section line

Lease Name HALL "F" Well # 1

Operator: KAISER-FRANCIS OIL Co
Name & Address 6733 So. YALE
Box 35528
Tulsa, OK 74135

County HODGEMAN

Well Total Depth 4606 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 243

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 176, Chase, KS 67524

Company to plug at: Hour: 2:00pm Day: 21 Month: DEC Year: 1982

VERBAL PLUGGING ORDERS GIVEN TO Buck Unruh

(company name) Kelso (phone) _____

were: Plug off gas w/ 1 1/2 sh hulls and 35 sy cement on bottom to 3910'. Recovered 2810' of 4 1/2". Use 50/50 Poz mix, 4% gel-3% C.C. and pump 3 sy. hulls, 15 sy gel, 70 sy. cement, 1 sy hulls, 15 sy gel and release 8 5/8 plug, then finish w/ 150 sy. cement orders by S. Derrant Signed R. Barlett (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1:00pm Day: 22 Month: Dec Year: 1982

ACTUAL PLUGGING REPORT May. press. 1200# - Shut in 500#
Plugged as ordered, except unable to release 8 5/8 plug. Cementing by Sun.

Remarks: 8 5/8 cemented w/ 150 sy. 4 1/2 set @ 4542 w/ 150 sy. cement. PBTD @ 4470. Perfs 4339-45 & 4362-66. RECEIVED 2810' STATE CORPORATION COMMISSION

DEC 29 1982

I hereby certify that the above plugging instructions were given as stated and that I (did / did not) observe this plugging.

INVOICED
1-12-83 Signed R. Barlett (TECHNICIAN)

WV. NO. 2093-W

FORM CP-2/3
Rev. 9-82