

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-~~083~~ 20104-0000

SE/4, Sec. 31, T23 S, R24 W/A
(SENESE) feet from N/S section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6568

feet from W/E section line

Lease Name Hall F Well # 2

Operator: Kaiser-Franco Oil Co.
Name & Address 6733 So. YALE
Box 35528
TULSA, OK 74135

County Hodgeman

Well Total Depth 4587 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 7/8 feet 278'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 176, Chase, KS 67524

Company to plug at: Hour: 1:00 PM Day: 21 Month: Dec. Year: 1982

VERBAL PLUGGING ORDERS GIVEN TO Buck Unruh

(company name) Kelso (phone)

were: sand the bottom to 4280 and top w/ 5 sy. cmt.
Recovered 3015' of 5 1/2", use 50/50 foam mix, 4% gel,
3% C.C. and pump 3 sy bulls, 15 sy gel, 70 sy cmt,
1 sy bulls, 15 sy gel and release 8 7/8 plug, then
finish w/ 150 sy cmt.

orders by S. Larrant

Signed R. Barhatten (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 4:25 PM Day: 21 Month: Dec Year: 1982

ACTUAL PLUGGING REPORT Plugged as ordered

Cementing by Sun. May. press. 1100#
Shut in press. 350#

Remarks: 5 1/2 @ 4579' w/ 125 sy cmt. BTDD @ 4524
Perfs @ 4323
8 7/8 cemented w/ 200 sy.

I hereby certify that the above plugging instructions were given as herein stated and that I (did / did not) observe this plugging.

RECEIVED
STATE CORPORATION COMMISSION
INVOICED
DATE 1-12-83
NOV. NO. 2092-W
DEC 29 1982
CONSERVATION DIVISION
Wichita Kansas

Signed R. Barhatten (TECHNICIAN)