

1052009

083-20082-0001  
Docket #E-16,908

To: STATE CORPORATION COMMISSION  
Wichita State Office Bldg. PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

1-23

API NUMBER 15-  
SW NE SW, SEC. 32, T 23 S, R 21 W/4E  
1650 feet from S section line  
3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 30884  
Operator: King Oil Inc.  
Name & Address: RR 1, Box 95  
Jetmore, KS 67854

Lease Name Gleason B Well # 2  
County Hodgeman 150.25  
Well Total Depth 4623 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 293

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well X SWD Well \_\_\_\_\_ O&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Cheyenne Well Service License Number 7146  
Address Ness City, KS

Company to plug at: Hour: 12 p.m. Day: 23 Month: 1 Year: 1996

Plugging proposal received from Moe  
(company name) Cheyenne Well Service (phone) 913-798-2282

Work: 5 1/2" at 4623' w/120 sx cement, PBD 4460', Perfs at 4358-59, 4430-40, 4514-84'  
1st plug pump 200 lbs. hulls and 25 sx cement to 4200',  
2nd plug perforate at 600' and pump 125 sx cement down 5 1/2",  
3rd plug pump 100 sx cement down 8 5/8" X 5 1/2" annulus,

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part \_\_\_\_\_ None \_\_\_\_\_  
Operations Completed: Hour: 3 p.m. Day: 23 Month: 1 Year: 1996

ACTUAL PLUGGING REPORT 1st plug pumped 200 lbs. hulls and 25 sx cement to 4200',  
2nd plug perforated at 600' and pumped 125 sx cement down 5 1/2" casing.

Maximum pressure 200 psi and shut in 100 psi on annulus.  
3rd plug pumped 100 sx cement down 8 5/8" X 5 1/2" annulus.

Remarks: Used 60/40 Pozmix 6% gel by Allied. No casing recovery.  
(if additional description is necessary, use BACK of this form)

RECEIVED COMM  
KANSAS CORP  
1996 JAN 26 P 12:18

Signed Richard M. Lacey (TECHNICIAN)

INVOICED  
DATE 1-30-96  
INV. NO. 44753

1-23