

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-165-21128-00-00
Spot: CSENESE Sec/Twnshp/Rge: 3-18S-18W
1650 feet from S Section Line, 330 feet from E Section Line
Lease/Unit Name: ERBES Well Number: 3
County: RUSH Total Vertical Depth: 3842 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: PO BOX 399
GARDEN CITY, KS 67846

Conductor Pipe: Size feet: 8/24.87
Surface Casing: Size 8.625 feet: 1224 WITH 300 SX CMT
Production: Size 5.5 feet: 3839 WITH 100 SX CMT
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 10/01/2001 10:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 278-2026

Proposed Plugging Method: SAND TO 3780' & 5 SX CMT. 1ST PLUG AT 1250' WITH 10 SX GEL - 50 SX CMT. 2ND PLUG AT 500' WITH 40 SX CMT. 3RD PLUG AT 0-40' WITH 10 SX CMT.

Plugging Proposal Received By: RICHARD LACEY Witness Type: Plugging Operations Were Not Witnessed
Date/Time Plugging Completed: 10/01/2001 12:00 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

OPEN HOLE 3839-3842'. SAND TO 3780' & 5 SX CMT. 1ST PLUG PUMPED 7 SX GEL - 50 SX CMT - 3 SX GEL AT 1250'. 2ND PLUG PULLED TO 500' & PUMPED 40 SX CMT. 3RD PLUG PULLED TO 40' & PUMPED 10 SX CMT.

Remarks: USED 60/40 POZMIX 6% GEL 1/4# FLO SEAL BY SWIFT SERVICES. RECOVERED 2830' OF 5 1/2" CASING.

Plugged through: CSG

District: 01

Signed Richard M. Lacey
(TECHNICIAN)

RECEIVED

INVOICED

OCT 11 2001

OCT 15 2001
10-15-01
KCC WICHITA

DATE 10-15-01
2002060807



