

To: 1 20859
STATE, CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

7-27 API NUMBER 15- 165-21,082-0000

SW SE NE, SEC. 3, T 18 S, R 18 W/E
2310 feet from NEX section line
990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5886

Lease Name Weigand Well # 2

Operator: Chief Drilling, Inc.

County Rush

Name & Address 120 S. Market, Ste. 300
Wichita, KS 67202

Well Total Depth 3827 124.37 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 1218

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Chief Drilling, Inc. License Number 5886

Address 120 S. Market, Ste. 300, Wichita, KS 67202

Company to plug at: Hour: 1 p.m. Day: 27 Month: 7 Year: 1993

Plugging proposal received from Gary Lindenmuth

(company name) Chief Drilling, Inc. (phone) 316-262-3791

were: 5 1/2" at 3825' w/125 sx cement, Open hole

1st plug sand 5 1/2" casing back to 3775' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper plug and pump 150 sx cement.

Plugging Proposal Received by Steve Middleton
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 4:45 p.m. Day: 27 Month: 7 Year: 1993

ACTUAL PLUGGING REPORT 1st plug sanded 5 1/2" casing back to 3775' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped in 8 5/8" surface casing with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 150 sx cement.

Maximum pressure 800 psi and shut in 500 psi

RECEIVED
STATE CORPORATION COMMISSION

7-30-93
JUL 30 1993

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2003' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION
WICHITA, KANSAS

INVOICED
AUG 04 1993

Observe this plugging.

Signed [Signature]
(TECHNICIAN)

DATE 38255