

TO: *
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-165-21003-00-00
Spot: CNWNES Sec/Twnshp/Rge: 3-18S-18W
330 feet from S Section Line, 990 feet from E Section Line
Lease/Unit Name: ERBES Well Number: 2
County: RUSH Total Vertical Depth: 3880 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: PO BOX 399
GARDEN CITY, KS 67846

Conductor Pipe: Size _____ feet: _____
Surface Casing: Size 8.625 feet: 1228 WITH 450 SX CMT **8/26.10**
Production: Size 5.5 feet: 3879 WITH 150 SX CMT
Liner: Size _____ feet: _____

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/03/2001 12:30 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 278-2026

Proposed Plugging Method: SAND TO 3821' WITH 5 SX CMT. 1ST PLUG AT 1250' WITH 50 SX CMT & 10 SX GEL. 2ND PLUG AT 500' WITH 40 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: RICHARD LACEY Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 10/03/2001 2:15 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

OPEN HOLE FROM 3879-80'. SANDED TO 3821' WITH 5 SX CMT. 1ST PLUG AT 1250' WITH 10 SX GEL - 50 SX CMT. 2ND PLUG AT 500' WITH 400 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Remarks: USED 60/40 POZMIX 6% GEL BY SWIFT SERVICES. RECOVERED 2421' OF 5 1/2" CASING.

Plugged through: DP

District: 01

Signed Michael Maier
(TECHNICIAN)

RECEIVED

10-11-01
OCT 11 2001

INVOICED

DATE 10-11-01

OCT 05 2001

KCC WICHITA

INV. NO. 2002060784

MP

[Signature]