

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-165-20954-00-00
Spot: CNENESE Sec/Twnshp/Rge: 3-18S-18W
330 feet from N Section Line, 990 feet from E Section Line
Lease/Unit Name: ERBES Well Number: 1
County: RUSH Total Vertical Depth: 3820 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: PO BOX 399
GARDEN CITY, KS 67846

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 1223 WITH 450 SX CMT 8124.15
Production: Size 4.5 feet: 3800 WITH 150 SX CMT
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 10/02/2001 10:30 AM

Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.

Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 278-2026

Proposed Plugging Method: SAND TO 3790' WITH 5 SX CMT. 1ST PLUG AT 1250' WITH 10 SX GEL - 50 SX CMT. 2ND PLUG AT 500' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: JIM HOLLAND

WitnessType: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 10/02/2001 2:30 PM

KCC Agent: MICHAEL MAIER

Actual Plugging Report:

OPEN HOLE FROM 3800-20'. 1ST PLUG SAND 4 1/2" TO 3721' & 5 SX CMT. 2ND PLUG PULLED 4 1/2" TO 1250'. PUMPED 8 SX GEL & 50 SX CMT. DETERMINE HOLE IN CASING AT 500'. 3RD PLUG PULLED 4 1/2" TO 500' PUMPED 125 SX CMT, CIRCULATED TO SURFACE. 4TH PLUG PULLED CASING TO 40' AND CIRCULATED HOLE TO SURFACE WITH 10 SX CMT. NOTE: 1ST PLUG IS AT 750' WITH 50 SX CMT.

Remarks: USED 60/40 POZMIX 6% GEL BY SWIFT SERVICES. RECOVERED 1520' OF 4 1/2" CASING.

Plugged through: CSG

District: 01

Signed Michael J Maier
(TECHNICIAN)

RECEIVED
10-11-01
OCT 11 2001
KCC WICHITA

INVOICED
DATE 10-11-01
INV. NO. 2002060784

OCT 05 2001

FORM CP-23

MP